


CONSTRUCTION DRAWINGS

PANTHER HOLLOW LAKE REHABILITATION PROJECT

CITY OF PITTSBURGH, ALLEGHENY COUNTY, PENNSYLVANIA

PREPARED FOR:

CITY OF PITTSBURGH, DEPARTMENT OF
PUBLIC WORKS-PARKS MAINTENANCE
DIVISION



SITE AERIAL PHOTO


- REFERENCE**
1. AERIAL HAS BEEN GENERATED REFERENCING GOOGLE EARTH
 2. APPROXIMATE SCALE 1"=500'

PREPARED BY:
CIVIL & ENVIRONMENTAL CONSULTANTS, INC.
333 BALDWIN ROAD
PITTSBURGH, PA 15205
412-429-2324
800-365-2324



AND

PITTSBURGH WATER & SEWER AUTHORITY
1200 PENN AVENUE
PITTSBURGH, PA 15222
OCTOBER 2019



VICINITY AERIAL PHOTO

- REFERENCE**
1. VICINITY MAP HAS BEEN GENERATED REFERENCING GOOGLE EARTH
 2. APPROXIMATE SCALE 1"=2.5 MILE

SHEET NO.	DESCRIPTION
G100	COVER SHEET
G101	GENERAL NOTES/LEGEND/ABBREVIATIONS
C100	EXISTING CONDITIONS PLAN
C200	SITE PREPARATION PLAN
C300	PROPOSED SITE GRADING PLAN
C301	LAKE EMBANKMENT PROFILE AND SECTION VIEWS - SHEET 1 OF 2
C302	LAKE EMBANKMENT PROFILE AND SECTION VIEWS - SHEET 2 OF 2
C400	PANTHER HOLLOW LAKE PRINCIPLE AND EMERGENCY SPILLWAY PLAN & PROFILE VIEW
C800	CONSTRUCTION DETAILS - SHEET 1 OF 4
C801	CONSTRUCTION DETAILS - SHEET 2 OF 4
C802	CONSTRUCTION DETAILS - SHEET 3 OF 3
C803	CONSTRUCTION DETAILS - SHEET 4 OF 4
C900	EROSION AND SEDIMENT CONTROL PLAN
C901	EROSION AND SEDIMENT CONTROL PLAN
C902	EROSION AND SEDIMENT CONTROL PLAN
C903	EROSION AND SEDIMENT CONTROL PLAN

P:\2017\174-960-CADD\DWG\C102 - Dam Permit\174960-C102-TITLE-SHEET.dwg(10/21/2019 4:53 PM) - User: jpm

REVISION RECORD	
NO	DESCRIPTION

Civil & Environmental Consultants, Inc.
333 Baldwin Road - Pittsburgh, PA 15205
Ph: 412.429.2324 - 800.365.2324 - Fax: 412.429.2114
www.cecinc.com

PITTSBURGH
PENNSYLVANIA
PGH₂O Pittsburgh Water & Sewer Authority

CITY OF PITTSBURGH
DEPARTMENT OF PUBLIC WORKS
PITTSBURGH WATER & SEWER AUTHORITY
PITTSBURGH, ALLEGHENY COUNTY, PA

DRAWN BY: CLR	CHECKED BY: JAL	APPROVED BY: PJS	
DATE: OCTOBER 2019	DWG SCALE: 	PROJECT NO: 174-960	
COVER SHEET PANTHER HOLLOW LAKE REHABILITATION PROJECT			DRAWING NO.: G100

GENERAL NOTES

- BEFORE ANY EARTHWORK ACTIVITIES ARE ALLOWED TO BEGIN ONSITE, THE CONTRACTOR SHALL CONTACT THE PENNSYLVANIA ONE CALL SYSTEM AT 1-800-962-7962 OR 811 A MINIMUM OF 3 DAYS PRIOR TO EARTHWORK ACTIVITIES TO ALLOW THE UTILITY COMPANIES TO MARK THE LOCATIONS OF EXISTING LINES OWNED AND MAINTAINED BY THE UTILITY COMPANIES.
- THE FOLLOWING PERMIT APPLICATIONS HAVE BEEN SUBMITTED FOR WORK TO BE PERFORMED UNDER THIS CONTRACT. THE OWNER HAS RECEIVED PERMISSION FROM THE APPROPRIATE AGENCY TO PROCEED WITH WORK IN ADVANCE OF PERMIT APPROVAL. THE CONTRACTOR SHALL FOLLOW ALL STIPULATIONS OF THE PERMIT APPLICATIONS.
 - NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT FROM PADEP FOR STORMWATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITIES.
 - STORMWATER POLLUTION PROTECTION PLAN (SWPPP).
 - EROSION AND SEDIMENT CONTROL PLAN.
 - PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION (PADEP) DAM PERMIT.
- EXISTING TOPOGRAPHY AND DIMENSIONS WERE OBTAINED FROM A COMPILATION OF TOPOGRAPHIC GROUND SURVEY AND GIS DATA INFORMATION. TOPOGRAPHIC ELEVATIONS AND DIMENSIONS SHOULD BE VERIFIED IN THE FIELD AND INVERTS SHOULD BE CHECKED IN THE FIELD AND REPORT ANY DISCREPANCIES TO THE OWNER AND THE OWNER'S REPRESENTATIVE PRIOR TO BEGINNING WORK.
- EXACT PLAN LOCATION, SURFACE ELEVATION, AND INVERT ELEVATION LOCATION OF ALL EXISTING UTILITIES SHOULD BE VERIFIED.
- A SMOOTH TRANSITION BETWEEN EXISTING PAVEMENT, GRAVEL AREAS OR TOPOGRAPHY, AND NEW PAVEMENT, GRAVEL AREAS OR TOPOGRAPHY SHOULD BE PROVIDED. FIELD ADJUSTMENT OF FINAL GRADES MAY BE NECESSARY.
- ONE SET OF AS-BUILT / RECORD DRAWINGS SHOULD BE MAINTAINED ON THE JOB SITE DURING CONSTRUCTION FOR DISTRIBUTION TO THE OWNER AND/OR OWNER'S REPRESENTATIVE UPON COMPLETION.
- EARTHWORK SHALL INCLUDE CLEARING AND GRUBBING, STRIPPING AND STOCKPILING TOPSOIL, GRADING, EXCAVATION, FILLING, UNDERCUT AND REPLACEMENT, AND COMPACTION.
- ALL AREAS NOT PAVED OR GRAVELED SHALL BE STABILIZED IN ACCORDANCE WITH THE SPECIFICATIONS, UNLESS NOTED OTHERWISE.
- DISTANCES SHOWN ON PIPING ARE HORIZONTAL DISTANCES FROM CENTER OF STRUCTURE TO CENTER OF STRUCTURE, UNLESS OTHERWISE NOTED.
- ALL STORMWATER MANAGEMENT FACILITIES, INCLUDING COLLECTION AND CONVEYANCE STRUCTURES, SHALL BE INSTALLED IN ACCORDANCE WITH ALL APPLICABLE STATE CODES AND REGULATIONS.
- REFER TO AND FOLLOW THE RECOMMENDATIONS OF THE "GEO TECHNICAL ENGINEERING REPORT" PREPARED FOR THIS PROJECT BY CIVIL & ENVIRONMENTAL CONSULTANTS, INC.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS ASSOCIATED WITH THE INSTALLATION, INSPECTION, TESTING AND FINAL ACCEPTANCE OF ALL NEW STORMWATER FACILITIES CONSTRUCTION. CONTRACTOR SHALL COORDINATE WITH ALL APPLICABLE REGULATING AGENCIES CONCERNING INSTALLATION, INSPECTION AND APPROVAL OF THE STORMWATER CONSTRUCTION.

LAYOUT GENERAL NOTES

- CARE SHALL BE TAKEN TO PROTECT UTILITIES THAT ARE TO REMAIN. RELOCATE EXISTING UTILITIES AS INDICATED, OR AS NECESSARY FOR CONSTRUCTION. INSTALL ALL UTILITIES, INCLUDING CONDUITS, PRIOR TO INSTALLATION OF PAVED SURFACES.
- PROVIDE A SMOOTH TRANSITION BETWEEN EXISTING PAVEMENT AND NEW PAVEMENT. FIELD ADJUSTMENT OF FINAL GRADES MAY BE NECESSARY.
- ALL DAMAGE TO EXISTING PAVEMENT TO REMAIN WHICH RESULTS FROM THE CONTRACTOR'S OPERATIONS SHALL BE REPLACED WITH LIKE MATERIALS AT THE CONTRACTOR'S EXPENSE.
- CONTRACTOR SHALL ADJUST THE PROPOSED ELEVATION AT THE TOP OF EXCAVATION SLOPES AS NEEDED TO TIE INTO EXISTING GROUND.
- CLEARING LIMITS SHALL BE PHYSICALLY MARKED IN THE FIELD.

DEMOLITION GENERAL NOTES

- ALL UTILITY DISCONNECTION, REMOVAL, RELOCATION, CUTTING, CAPPING AND/OR ABANDONMENT SHALL BE COORDINATED WITH THE APPROPRIATE UTILITY COMPANY/AGENCY. UTILITY CONTACTS ARE LISTED BELOW.
- CONTRACTOR SHALL PROTECT ALL CORNER PINS, MONUMENTS, PROPERTY CORNERS AND BENCHMARKS DURING DEMOLITION ACTIVITIES. IF DISTURBED, CONTRACTOR SHALL HAVE DISTURBED ITEMS RESET BY A LICENSED SURVEYOR AT NO ADDITIONAL COST TO THE OWNER.
- CONTRACTOR SHALL PROTECT ALL EXISTING UTILITIES, STRUCTURES, AND FEATURES TO REMAIN. ANY ITEMS TO REMAIN THAT HAVE BEEN DISTURBED OR DAMAGED AS A RESULT OF CONSTRUCTION SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR AT NO ADDITIONAL COST TO OWNER.
- CONTRACTOR SHALL PROVIDE AND MAINTAIN TRAFFIC CONTROL MEASURES IN ACCORDANCE WITH STATE DEPARTMENT OF TRANSPORTATION REGULATIONS AND AS REQUIRED BY LOCAL AGENCIES WHEN WORKING IN AND/OR ALONG STREETS, ROADS, HIGHWAYS, ETC. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN APPROVAL AND COORDINATE WITH LOCAL AND/OR STATE AGENCIES REGARDING THE NEED, EXTENT AND LIMITATIONS ASSOCIATED WITH INSTALLING AND MAINTAINING TRAFFIC CONTROL MEASURES.
- PROVIDE NEAT, STRAIGHT, FULL DEPTH, SAW CUTS OF EXISTING PAVEMENT WHERE INDICATED ALONG LIMITS OF PAVEMENT DEMOLITION.
- ALL UTILITY AND STRUCTURE REMOVAL, RELOCATION, CUTTING, CAPPING AND/OR ABANDONMENT SHALL BE COORDINATED AND PROPERLY DOCUMENTED BY A CERTIFIED PROFESSIONAL, WHEN APPLICABLE, WITH THE APPROPRIATE UTILITY COMPANY, MUNICIPALITY AND/OR AGENCY.
- NO TREES SHALL BE REMOVED, NOR VEGETATION DISTURBED BEYOND THE LIMITS OF CONSTRUCTION WITHOUT THE EXPRESS WRITTEN APPROVAL OF THE OWNER'S REPRESENTATIVE.
- THE CONTRACTOR SHALL USE SUITABLE METHODS TO CONTROL DUST AND DIRT CAUSED BY THE DEMOLITION ACTIVITY.

UTILITY GENERAL NOTES

- ALL PROPOSED UTILITY LINES AND EXTENSIONS ARE TO BE CONSTRUCTED IN ACCORDANCE WITH ALL APPLICABLE UTILITY COMPANY SPECIFICATIONS. CONTRACTOR SHALL COORDINATE UTILITY DISCONNECTIONS WITH THE APPROPRIATE AGENCY.
- THE CONTRACTOR IS PARTICULARLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF THE EXISTING UTILITIES SHOWN HEREON IS BASED ON TOPOGRAPHIC SURVEYS AND RECORD DRAWINGS. THE CONTRACTOR SHALL NOT RELY UPON THIS INFORMATION AS BEING EXACT OR COMPLETE. SHOULD UNCHARTED UTILITIES BE ENCOUNTERED DURING EXCAVATION OPERATIONS, THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY FOR INSTRUCTIONS. THE CONTRACTOR SHALL CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION AND REQUEST FIELD VERIFICATION OF UTILITY LOCATIONS.
- THE CONTRACTOR SHALL OBTAIN ALL REQUIRED UTILITY WORK PERMITS PRIOR TO COMMENCEMENT OF CONSTRUCTION.
- THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING THE SEQUENCING OF CONSTRUCTION FOR ALL UTILITY LINES SO THAT WATER LINES AND UNDERGROUND ELECTRIC CONDUITS DO NOT CONFLICT WITH SANITARY SEWERS OR STORM SEWERS. INSTALL UTILITIES PRIOR TO PAVEMENT CONSTRUCTION.
- ADJUST ALL EXISTING UTILITY SURFACE FEATURES INCLUDING BUT NOT LIMITED TO CASTINGS, VALVE BOXES, PEDESTALS, CLEANOUTS, ETC. TO MATCH PROPOSED FINISHED GRADES, UNLESS OTHERWISE INDICATED.
- CONTRACTOR IS TO COORDINATE WITH EACH UTILITY PROVIDER REGARDING INSTALLATION OF UTILITY CONDUITS FOR ELECTRICAL WORK. CONTRACTOR SHALL PROVIDE ALL MATERIALS AND LABOR FOR THE TRENCHING AND CONDUIT INSTALLATION. COST FOR INSTALLATION AND MATERIALS SHALL BE INCLUDED IN VARIOUS BID ITEMS.

DATUM AND TOPOGRAPHIC SURVEY

VERTICAL DATUM: NAVD88 (GEIOD 12A)

HORIZONTAL DATUM: NAD83 NORTH ZONE (2011)

BENCHMARKS TABLE:

CONTROL POINTS			
CONTROL POINT NO.	NORTHING	EASTING	ELEVATION
16	1356619.682'	409503.329'	811.576'
17	1357146.573'	409614.972'	816.632'
1000	1356377.623'	409670.92'	808.985'
1001	1356664.538'	409548.924'	806.256'

DATUM NOTES:

- SITE BENCHMARKS OBTAINED FROM AWK CONSULTING ENGINEERS, INC. USING GROUND SURVEY TECHNIQUES IN MAY 2018.

REFERENCE

- PANTHER HOLLOW LAKE BATHYMETRICAL SURVEY PERFORMED BY AWK CONSULTING ENGINEERS, INC., DATED OCTOBER 2017.
- POTHOLING UTILITY INVESTIGATION PERFORMED BY TERRA TESTING INC., DATED OCTOBER AND NOVEMBER 2018.
- EXISTING TOPOGRAPHY AND CONTOURS DERIVED FROM PHOTOGRAMETRY SURVEY PERFORMED BY LAND MAPPING, INC. DATED NOVEMBER 2016, AWK CONSULTING ENGINEERS, INC. FIELD SURVEY, DATED JUNE 2018, CIVIL & ENVIRONMENTAL CONSULTANTS, INC. FIELD SURVEY, DATED JULY-AUGUST 2018, AND ALLEGHENY COUNTY, PA LIDAR, DATED 2017.
- STREAM AND WETLAND DELINEATION PERFORMED BY CIVIL & ENVIRONMENTAL CONSULTANTS, INC. DATED MAY-JULY 2018.

STANDARD ABBREVIATIONS

ACI	AMERICAN CONCRETE INSTITUTE	NAVD	NORTH AMERICAN VERTICAL DATUM
ALT	ALTERNATE	NGVD	NATIONAL GEODETIC VERTICAL DATUM
APPROX	APPROXIMATE	NO	NUMBER
ASTM	AMERICAN SOCIETY FOR TESTING AND MATERIALS	NTS	NOT TO SCALE
B.O.	BY OTHERS	O&M	OPERATION AND MAINTENANCE
¢	CENTERLINE	OD	OUTSIDE DIAMETER
C	CAST-IN-PLACE, CAST IRON PIPE	OPNG	OPENING
CIP	CONCRETE	PA	PENNSYLVANIA
CONC	CONTRACTOR WORK LIMITS	PI	POINT OF INTERSECTION
CWL	CUBIC YARD	PSF	POUNDS PER SQUARE FOOT
CY	DIAMETER	PSI	POUNDS PER SQUARE INCH
DIA	DRAWING	PT	POINT
DWG	EROSION AND SEDIMENT	PVI	POINT OF VERTICAL INTERSECTION
E&S	ELEVATION	PVT	POINT OF VERTICAL TANGENCY
EL	EXISTING	REINF	REINFORCEMENT
EXIST	FOOT, FEET	REQ'D	REQUIRED
FT	GAGE	SCH	SCHEDULE
GA	HIGH-DENSITY POLYETHYLENE	STA	STATION
HDPE	HORIZONTAL	STD	STANDARD
HORIZ	INCH, INCHES	TYP	TYPICAL
IN	POUND, POUNDS	UNO	UNLESS NOTED OTHERWISE
LB	LIMITS OF DISTURBANCE	VERT	VERTICAL
LOD	MAXIMUM	WP	WORK POINT
MAX	MINIMUM		
MIN	MISCELLANEOUS		
MISC	NOT APPLICABLE		
N/A	NORTH AMERICAN DATUM		
NAD			

STANDARD LEGEND

	EXISTING PROPERTY LINE
	EXISTING BUILDING
	EXISTING AUXILIARY BUILDING
	EXISTING INDEX CONTOUR
	EXISTING INTERMEDIATE CONTOUR
	EXISTING CURB
	EXISTING EDGE ROAD
	EXISTING EDGE OF SIDEWALK
	EXISTING EDGE OF CONCRETE TRAIL
	EXISTING EDGE OF UNPAVED TRAIL
	EXISTING EDGE OF PAVED DRIVEWAY
	EXISTING ROAD CENTERLINE
	EXISTING BRIDGE
	EXISTING RAILROAD
	EXISTING WALL
	EXISTING BODY OF WATER
	EXISTING STREAM
	EXISTING GUIDERAIL
	EXISTING FENCE
	EXISTING TREE/SHRUB LINE
	EXISTING TREE
	EXISTING POST/SIGN
	EXISTING GIS WETLAND
	PROPOSED PAVED LIMITS
	PROPOSED ROADSIDE DITCH
	PROPOSED WETLAND
	PROPOSED INDEX CONTOUR
	PROPOSED INTERMEDIATE CONTOUR
	PROPOSED STORM SEWER LINE
	PROPOSED RIPRAP OUTFALL APRON
	PROPOSED HEADWALL/ENDWALL
	PROPOSED WATERLINE
	GEO TECHNICAL BORING LOCATION
	PIEZOMETER INSTALLATION LOCATION
	PROPOSED CONTRACTOR LIMITS OF DISTURBANCE
	CONCRETE
	EARTH
	GRAVEL
	RIPRAP

P:\2017\174-960-CADD\DWG\CH02 - Dam Permit\174960-C101-GEN NOTES.mxd(10/15/2019 4:03 PM) - ebsky


REVISION RECORD		
NO	DATE	DESCRIPTION

CEC
Civil & Environmental Consultants, Inc.
333 Baldwin Road - Pittsburgh, PA 15205
Ph: 412.429.2324 - 800.365.2324 - Fax: 412.429.2114
www.cecinc.com


PITTSBURGH
PENNSYLVANIA
PGH₂O Pittsburgh Water & Sewer Authority

CITY OF PITTSBURGH
DEPARTMENT OF PUBLIC WORKS
PITTSBURGH WATER & SEWER AUTHORITY
PITTSBURGH, ALLEGHENY COUNTY, PA


DRAWN BY: CLR	CHECKED BY: JAL	APPROVED BY: PJS
DATE: OCTOBER 2019	DWG SCALE: AS-SHOWN	PROJECT NO: 174-960
GENERAL NOTES/LEGEND/ABBREVIATIONS PANTHER HOLLOW LAKE REHABILITATION PROJECT		DRAWING NO.: G101



NORTH



SITE PREPARATION PLAN



F:\2017\174-960-CAD\DWG\C200 - Civil & Environmental Consultants, Inc. - 10/21/2019 4:12 PM
 F:\2017\174-960-CAD\DWG\C200 - Civil & Environmental Consultants, Inc. - 10/21/2019 4:12 PM
 F:\2017\174-960-CAD\DWG\C200 - Civil & Environmental Consultants, Inc. - 10/21/2019 4:12 PM


REVISION RECORD		
NO	DATE	DESCRIPTION

CEC
 Civil & Environmental Consultants, Inc.
 333 Baldwin Road - Pittsburgh, PA 15205
 Ph: 412.429.2324 - 800.365.2324 Fax: 412.429.2114
 www.cecinc.com


PITTSBURGH
 PENNSYLVANIA
PGH₂O Pittsburgh Water & Sewer Authority

CITY OF PITTSBURGH
 DEPARTMENT OF PUBLIC WORKS
 PITTSBURGH WATER & SEWER AUTHORITY
 PITTSBURGH, ALLEGHENY COUNTY, PA

DRAWN BY: CLR	CHECKED BY: JAL	APPROVED BY: PJS
DATE: OCTOBER 2019	DWG SCALE: 1"=30'	PROJECT NO: 174-960
SITE PREPARATION PLAN PANTHER HOLLOW LAKE REHABILITATION PROJECT		DRAWING NO.: C200



PANTHER HOLLOW LAKE AND FOREBAY POND PLAN



REVISION RECORD		
NO.	DATE	DESCRIPTION

CEC
Civil & Environmental Consultants, Inc.
 333 Baldwin Road - Pittsburgh, PA 15205
 Ph: 412.429.2324 - 800.365.2324 Fax: 412.429.2114
 www.cecinc.com


PITTSBURGH PENNSYLVANIA
PGH₂O Pittsburgh Water & Sewer Authority

CITY OF PITTSBURGH
DEPARTMENT OF PUBLIC WORKS
PITTSBURGH WATER & SEWER AUTHORITY
PITTSBURGH, ALLEGHENY COUNTY, PA

DRAWN BY: CLR	CHECKED BY: JAL	APPROVED BY: PJS
DATE: OCTOBER 2019	DWG SCALE: 1"=30'	PROJECT NO: 174-960
DRAWING NO.: C300		


PROPOSED SITE GRADING PLAN
 PANTHER HOLLOW LAKE DAM RESTORATION
 AND FOREBAY POND

F:\2017\174-960-CAD\DWG\C300 - Dam Permit\174960-C101-C300.dwg (C300) LS(10/21/2019 4:35 PM) - LF: 10/21/2019 4:35 PM





PANTHER HOLLOW LAKE - LONGITUDINAL SECTION A

SCALE H:1"=30'; V:1"=15'




PANTHER HOLLOW LAKE - SECTION B

SCALE H:1"=30'; V:1"=30'



PANTHER HOLLOW LAKE - SECTION C

SCALE H:1"=30'; V:1"=30'



P:\2017\174-960-CAD\DWG\C301 - 10/21/2019 4:56 PM


REVISION RECORD		
NO	DATE	DESCRIPTION

CEC
Civil & Environmental Consultants, Inc.
 333 Baldwin Road - Pittsburgh, PA 15205
 Ph: 412.429.2324 - 800.365.2324 - Fax: 412.429.2114
 www.cecinc.com


PITTSBURGH
 PENNSYLVANIA
PGH₂O Pittsburgh Water & Sewer Authority

CITY OF PITTSBURGH
 DEPARTMENT OF PUBLIC WORKS
PITTSBURGH WATER & SEWER AUTHORITY
 PITTSBURGH, ALLEGHENY COUNTY, PA


DRAWN BY: CLR	CHECKED BY: JAL	APPROVED BY: PJS
DATE: OCTOBER 2019	DWG SCALE: AS-SHOWN	PROJECT NO: 174-960
PANTHER HOLLOW LAKE SECTION VIEWS		
PANTHER HOLLOW LAKE REHABILITATION PROJECT		
DRAWING NO.:		C301




PANTHER HOLLOW LAKE - EMBANKMENT PROFILE
SCALE H:1"=30'; V:1"=30'




LAKE EMBANKMENT - SECTION D
SCALE H:1"=30'; V:1"=30'




LAKE EMBANKMENT - SECTION E
SCALE H:1"=30'; V:1"=30'



LAKE EMBANKMENT - SECTION F
SCALE H:1"=30'; V:1"=30'



LAKE EMBANKMENT - SECTION G
SCALE H:1"=30'; V:1"=30'



REVISION RECORD		
NO	DATE	DESCRIPTION




CEC
Civil & Environmental Consultants, Inc.
333 Baldwin Road - Pittsburgh, PA 15205
Ph: 412.429.2324 - 800.365.2324 - Fax: 412.429.2114
www.cecinc.com

PITTSBURGH
PENNSYLVANIA
PGH₂O Pittsburgh Water & Sewer Authority

CITY OF PITTSBURGH
DEPARTMENT OF PUBLIC WORKS
PITTSBURGH WATER & SEWER AUTHORITY
PITTSBURGH, ALLEGHENY COUNTY, PA

DRAWN BY: CLR	CHECKED BY: JAL	APPROVED BY: PJS
DATE: OCTOBER 2019	DWG SCALE: AS-SHOWN	PROJECT NO: 174-960
LAKE EMBANKMENT PROFILE AND SECTION VIEWS PANTHER HOLLOW LAKE REHABILITATION PROJECT		DRAWING NO.: C302

P:\2017\174-960-C302\Drawings\174-960-C302.dwg [C302] LS(10/21/2019 - crasse) - LF: 10/21/2019 4:59 PM



REVISION RECORD		
NO	DATE	DESCRIPTION


CEC
Civil & Environmental Consultants, Inc.
333 Baldwin Road - Pittsburgh, PA 15205
Ph: 412.429.2324 - 800.365.2324 - Fax: 412.429.2114
www.cecinc.com

PITTSBURGH PENNSYLVANIA
PGH₂O Pittsburgh Water & Sewer Authority


CITY OF PITTSBURGH
DEPARTMENT OF PUBLIC WORKS
PITTSBURGH WATER & SEWER AUTHORITY
PITTSBURGH, ALLEGHENY COUNTY, PA

DRAWN BY: CLR | CHECKED BY: JAL | APPROVED BY: PJS
DATE: OCTOBER 2019 | DWG SCALE: | PROJECT NO: 174-960
DRAWING NO.: **C400**
PANTHER HOLLOW LAKE PRINCIPAL AND EMERGENCY SPILLWAY PLAN & PROFILE VIEW



F:\2017\174-960-C400-CD02.dwg | C:\202 - Dam Permit\174960-C101-C400.dwg | LS(10/21/2019 - cress) - LF: 10/21/2019 4:47 PM





DETAIL 1
RISER STRUCTURE PLAN AND REINFORCEMENT
SCALE 3/8" = 1'-0"



SECTION A-A
SCALE 3/8" = 1'-0"




DETAIL 2
THRUST BLOCK - PLAN
N.T.S.




TYPE 1 CAST-IN-PLACE
TYPE 2 PRE-DRILLED HOLE
NOTES:
1. TYPICAL STEPS, SPACING AND MATERIAL AS PER ASTM DESIGNATION C-478, AASHTO M-199.
2. PLASTIC SHALL BE A CO-POLYMER POLYPROPYLENE MEETING THE REQUIREMENTS OUTLINED IN ASTM DESIGNATION D-4101 UNDER TYPE II, GRADE 49108.
3. STEEL REINFORCING BAR SHALL BE A 1/2" (13mm) DEFORMED BAR, GRADE 60 AND CONFORMING TO THE REQUIREMENTS OF ASTM DESIGNATION A-615.
4. USE TYPE 1 FOR CAST-IN-PLACE VAULTS. USE TYPE 2 FOR NEW PRECAST MANHOLES OR WHEN ADDING STEPS TO EXISTING STRUCTURES.
5. ALL STEPS SHALL BE SET VERTICALLY AT 12" CENTER TO CENTER.

DETAIL 3
PLASTIC MANHOLE STEP
N.T.S.



DETAIL 4
PRE-CAST CONCRETE MANHOLE
N.T.S.

- NOTES:**
- CONSTRUCT IN ACCORDANCE WITH THE REQUIREMENTS OF COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF TRANSPORTATION (PADOT) PUBLICATION 408, SECTION 605.
 - REFER TO PADOT BUREAU OF HIGHWAY DESIGN'S STANDARDS FOR ROADWAY CONSTRUCTION, SERIES RC-1 TO RC-100, SHEETS 1 THROUGH 5 OF RC-39, FOR DETAILS OF THE MANHOLE SECTIONS, GRADE ADJUSTMENT RINGS, STEPS, FRAMES AND COVERS.
 - ALL CEMENT CONCRETE USED TO CONSTRUCT THE MANHOLES SHALL BE CLASS AA, AND SATISFY THE REQUIREMENTS OF PADOT PUBLICATION 408, SECTION 704.
 - ALL REINFORCEMENT STEEL USED TO CONSTRUCT THE MANHOLES SHALL BE ASTM-A615, GRADE 60, DEFORMED OR PLAIN STEEL BARS, AND SATISFY THE REQUIREMENTS OF PADOT PUBLICATION 408, SECTION 709.1 AND 709.2 (IF APPLICABLE).
 - PRE-CAST REINFORCED CONCRETE MANHOLE SECTIONS AND GRADE ADJUSTMENT RINGS SHALL CONFORM TO THE REQUIREMENTS OF PADOT PUBLICATION 408, SECTION 714, AND HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3,500 PSI.
 - ALL FRAMES AND COVERS/GRATES FOR STORM SEWER AND SANITARY SEWER MANHOLES SHALL BE NON-ROCKING AND MADE OF HEAVY DUTY CAST IRON, AND SATISFY THE REQUIREMENTS OF PADOT PUBLICATION 408, SECTION 605.2(b). ALL FRAMES SHALL BE SET IN A FULL BED OF MORTAR AND ANCHORED TO THE CONICAL TOP SECTION USING MINIMUM 4 ANCHOR BOLTS ON OPPOSITE SIDES.
 - ALL GRADE ADJUSTMENT RINGS SHALL BE OF MASONRY OR PRECAST CONCRETE CONSTRUCTION.
 - A RUBBER GASKET THAT SATISFIES THE REQUIREMENTS OF ASTM C-443 SHALL BE INSTALLED BETWEEN ALL STORM SEWER MANHOLE SECTIONS. INSTALL TWO CONTINUOUS RINGS OF BITUMINOUS MASTIC THAT SATISFY ASTM C-443 AT EACH JOINT FOR SANITARY SEWER MANHOLES.
 - ALL MANHOLE SECTIONS SHALL BE SET IN PLACE IN NON-SHRINK MORTAR OR BITUMINOUS MATERIAL AND CONFORM TO THE REQUIREMENTS OF PADOT PUBLICATION 408, SECTION 705.7.
 - ALL MANHOLES SHALL HAVE LADDER RUNGS, SPACED 12 INCHES APART, TO FACILITATE ACCESS TO THE MANHOLE. ALL LADDER RUNGS SHALL BE MINIMUM NO. 4 REINFORCEMENT BARS THAT ARE COATED WITH CO-POLYMER POLYPROPYLENE PLASTIC THAT MEET THE REQUIREMENTS OF PADOT PUBLICATION 408, SECTION 605.2(c). ALL LADDER RUNGS MUST MEET THE PERFORMANCE CRITERIA OF ASTM C478.
 - A MINIMUM OF 12" OF AASHTO #57 STONE SHALL BE USED AS BEDDING FOR THE MANHOLES. THE AASHTO #57 STONE SHALL BE PLACED IN MAXIMUM 6-INCH THICK LOOSE LIFTS AND COMPACTED TO AT LEAST 75% OF ITS RELATIVE DENSITY. ALL AASHTO #57 STONE SHALL BE CRUSHED LIMESTONE AND SATISFY THE REQUIREMENTS OF PADOT PUBLICATION 408, SECTION 703. ALL SOIL BACKFILL PLACED AROUND THE MANHOLES, AND ABOVE THE BEDDING, SHALL BE PLACED IN MAXIMUM 8-INCH THICK LOOSE LIFTS AND COMPACTED TO AT LEAST 95% OF ITS MAXIMUM DRY DENSITY AND WITHIN ±3% OF ITS OPTIMUM MOISTURE CONTENT AS DETERMINED BY ASTM D1557 (MODIFIED PROCTOR).
 - A FLEXIBLE RUBBER MANHOLE SLEEVE OR BOOT SHALL BE INSTALLED IN THE PIPE OPENINGS FOR THE SANITARY SEWER MANHOLES BY THE MANHOLE MANUFACTURER PRIOR TO SITE DELIVERY. THE SANITARY SEWER PIPE SHALL BE SECURED TO THE SLEEVE/BOOT USING STAINLESS STRAPPING UPON INSTALLATION. ANNUAL AREA BETWEEN PIPE OPENING AND CONCRETE BASE SHALL BE RAMMED WITH EMBECO GROUT.



DETAIL 5
DEWATERING BYPASS CHANNEL
N.T.S.

REVISION RECORD		
NO.	DATE	DESCRIPTION


CEC
Civil & Environmental Consultants, Inc.
333 Baldwin Road - Pittsburgh, PA 15205
Ph: 412.429.2324 - 800.365.2324 - Fax: 412.429.2114
www.cecinc.com

PITTSBURGH
PENNSYLVANIA
PGH₂O Pittsburgh Water & Sewer Authority


CITY OF PITTSBURGH
DEPARTMENT OF PUBLIC WORKS
PITTSBURGH WATER & SEWER AUTHORITY
PITTSBURGH, ALLEGHENY COUNTY, PA

DRAWN BY: CLR	CHECKED BY: JAL	APPROVED BY: PJS
DATE: OCTOBER 2019	DWG SCALE:	PROJECT NO: 174-960
SITE CONSTRUCTION DETAILS		DRAWING NO: C800


P:\2017\174-960-C800-0101-C800.dwg | C:\Users\jwalsh\OneDrive\Documents\174960-0101-C800.dwg | LS(10/21/2019 4:28 PM) - LF: 10/21/2019 4:28 PM



**DETAIL 7
LOW LEVEL OUTLET**
N.T.S.




**DETAIL 7
LOW LEVEL OUTLET**
N.T.S.




**SECTION A-A
SECTION B-B**
N.T.S.


Zone 1: Semi-Submerged	Zone 2: Transitional	Zone 3: Water's Edge	Zone 4: Upland
Zone 1A Submerged Aquatics: Chelone glabra Nuphar spp. Utricularia spp. Bladderwort species	Flowering: Chelone glabra Hibiscus moscheutos Iris versicolor Mimulus ringens Sedges and Rushes: Carex comosa Carex crinita Carex lurida Carex stricta Carex vulpinoidea Juncus: Juncus canadensis Juncus tenuis Juncus torreyi Barrier Plants: Cephalanthus occidentalis Leersia oryzoides Rosa palustris	Flowering: Asclepias incarnata Aster novi-belgii Chelone glabra Eupatorium perfoliatum Hibiscus moscheutos Iris versicolor Lobelia cardinalis Verbena hastata Sedges, Rushes, and Grasses: Elymus virginicus Juncus effusus Scirpus cyperinus Scirpus pungens Barrier Plants: Cephalanthus occidentalis Clethra alnifolia Cornus sericea Ilex verticillata Rhododendron viscosum Salix discolor	Flowering: Aster novae-angliae Eupatorium coelestinum Eupatorium purpureum Rudbeckia hirta Grasses: Andropogon gerardii Panicum virgatum Schizachyrium scoparium Sorghastrum nutans Barrier Plants: Clethra alnifolia Cornus amomum




**DETAIL 6
EMERGENCY SPILLWAY SECTION AND REINFORCEMENT**
N.T.S.



**DETAIL 8
NARROW AQUATIC BENCH**
SCALE 1"=10'



**DETAIL 9
WETLAND CROSS SECTION**
SCALE 1"=10'



SECTION C-C
N.T.S.

REVISION RECORD		
NO.	DATE	DESCRIPTION


CEC
Civil & Environmental Consultants, Inc.
333 Baldwin Road - Pittsburgh, PA 15205
Ph: 412.429.2324 • 800.365.2324 • Fax: 412.429.2114
www.cecinc.com

PITTSBURGH
PENNSYLVANIA
PGH₂O Pittsburgh Water & Sewer Authority


CITY OF PITTSBURGH
DEPARTMENT OF PUBLIC WORKS
PITTSBURGH WATER & SEWER AUTHORITY
PITTSBURGH, ALLEGHENY COUNTY, PA

DRAWN BY: **CLR** / CHECKED BY: **JAL** / APPROVED BY: **PJS**
DATE: **OCTOBER 2019** / DWG SCALE: **AS-SHOWN** / PROJECT NO: **174-960**
DRAWING NO.: **C801**
SITE CONSTRUCTION DETAILS


P:\2017\174-960-C801-C800.dwg | LS(10/21/2019 4:52 PM) - LP: 10/21/2019 4:52 PM




DETAIL 10
FINISHED GRADE DETAIL
N.T.S.



DETAIL 11
BENCHING DETAIL
N.T.S.




DETAIL 12
FILTER DIAPHRAM DETAIL
N.T.S.



PROFILE ALONG CENTERLINE OF CONDUIT

FILTER MATERIAL GRADATION	
SIEVE SIZE	% PASSING BY WEIGHT
3/8 IN.	100
NO. 4	95-100
NO. 16	45-85
NO. 50	5-30
NO. 100	0-10

ASTM, C-33 FINE AGGREGATE



SECTION B-B


SECTION C-C

PARTIAL ISOMETRIC


NOTES:

- THE FILTER MATERIAL SHALL BE PLACED IN 6 INCH LIFTS AND COMPACTED WITH ONE PASS OF A PLATE VIBRATOR.
- FILTER DIAPHRAM SHALL BE LOCATED DOWNSTREAM FROM EMBANKMENT CENTERLINE A MAXIMUM DISTANCE AS POSSIBLE TO ACHIEVE A MINIMUM COVER OF 2 FEET.

DETAIL 14
NOT USED
N.T.S.




DETAIL 13
PRINCIPAL SPILLWAY PIPE AND LOW LEVEL OUTLET PIPE TRENCH
N.T.S.



NOTES:

- FIRE HYDRANT INSTALLATION SHALL BE IN ACCORDANCE WITH THE MUNICIPAL AUTHORITY AND PETERS TOWNSHIP FIRE DEPARTMENT REQUIREMENTS AND SPECIFICATIONS OF PA AMERICAN WATER COMPANY.
- ALL FITTINGS, VALVES, AND HYDRANTS SHALL BE POLYETHYLENE WRAPPED.
- FIRE HYDRANT TO MEET TOWNSHIP REQUIREMENT OF 6" FULL FLOW.

DETAIL 15
TYPICAL FIRE HYDRANT INSTALLATION
N.T.S.



SECTION A-A

DETAIL 16
LAKE EMERGENCY SPILLWAY
N.T.S.

REVISION RECORD		
NO.	DATE	DESCRIPTION


C&E
Civil & Environmental Consultants, Inc.
333 Baldwin Road - Pittsburgh, PA 15205
Ph: 412.429.2324 - 800.365.2324 - Fax: 412.429.2114
www.cecinc.com

PITTSBURGH
PENNSYLVANIA
PGH₂O Pittsburgh Water & Sewer Authority

CITY OF PITTSBURGH
DEPARTMENT OF PUBLIC WORKS
PITTSBURGH WATER & SEWER AUTHORITY
PITTSBURGH, ALLEGHENY COUNTY, PA

DRAWN BY: CLR	CHECKED BY: JAL	APPROVED BY: PJS
DATE: OCTOBER 2019	DWG SCALE: AS-SHOWN	PROJECT NO: 174-960
SITE CONSTRUCTION DETAILS		DRAWING NO.: C802

P:\2017\174-960-C802-Dwg\C802 - Dam Permit\174960-C802.dwg (2/22) LS(10/21/2019 4:53 PM) - LF: 10/21/2019 4:53 PM



S:\customers\2019\19-840_CEC_MWP\6_Engineering-Permitting\From CEC CAD Database\From CEC CAD Database\17486000-C900-PLAN\LS(10/18/2019 - Revision) - LP: 10/21/2019 12:05 PM

LEGEND

- COMPOST FILTER SOCK NUMBER, REFER TO C5-301 FOR SCHEDULE
- COMPOST FILTER SOCK
- LIMIT OF DISTURBANCE
- ROCK CONSTRUCTION ENTRANCE
- SOIL DELINEATION
- DUST COVERS
- INLET FILTER MAT
- CONCRETE WASHOUT
- PUMPED WATER FILTER BAG
- SOIL TYPE
- EROSION CONTROL BLANKET
- ROCK CONSTRUCTION ENTRANCE
- MATERIAL AND EQUIPMENT STAGING AREA
- SOIL STOCKPILE AREA

811 Pennsylvania One Call System, Inc.
 Call 3 Business Days Before You Dig!
 1-800-242-1776 or 8-1-1
 POCs Serial NO. _____
 Date: _____


CONTRACTORS ARE REQUIRED TO NOTIFY THE FACILITY OWNERS NOT LESS THAN THREE (3) NOT MORE THAN TEN (10) WORKING DAYS PRIOR TO EXCAVATION OR DEMOLITION WORK WHEN USING POWERED EQUIPMENT ON PUBLIC OR PRIVATE PROPERTY ANYWHERE IN THE COMMONWEALTH. CONTRACTORS ARE RESPONSIBLE FOR PRESERVING THE FACILITY OWNER MARKINGS, TO EXERCISE DUE CARE AND EMPLOY PRUDENT TECHNIQUES WITHIN THE TOLERANCE ZONE. CONTRACTORS SHOULD KEEP EACH OPERATOR AT THE SITE INFORMED AND EVALUATE THE PREMISES IF NECESSARY. NOTIFICATION SHOULD BE MADE THROUGH THE PENNSYLVANIA ONE-CALL SYSTEM (1-800-242-1776 or 8-1-1).

SYMBOL	SOIL TYPE
URB	URBAN LAND-RAINBORO COMPLEX, GENTLY SLOPING, HYDROLOGIC SOIL GROUP C
UB	URBAN LAND
GQF	GILPIN-UPSHUR COMPLEX, VERY STEEP, HYDROLOGIC SOIL GROUP C

OFF-SITE RECEIVING WATERS OF THE COMMONWEALTH
 UNT TO MONONGAHELA RIVER ID: 134839843 - WARM WATER FISHES (WWF)
 WATERSHED: LOWER MONONGAHELA
 REFERENCE: PA eMap

SOCK NO.	DIAMETER (IN.)	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT.)
1	18	33	12
2	18	7	93
3	18	33	12

REFERENCE: PADEP E&S MANUAL STANDARD E&S WORKSHEET NO. 1



DRAFT

PRELIMINARY NOT FOR CONSTRUCTION

REVISION RECORD		
NO	DATE	DESCRIPTION


Schiek CONSULTANTS, INC.
 1880 JOHN F. KENNEDY BLVD., SUITE 600
 PHILADELPHIA, PA 19103
 PHONE: (267) 341-5385 FAX: (267) 619-0273
 www.schiekconsultants.com

Civil & Environmental Consultants, Inc.
 333 Baldwin Road • Pittsburgh, PA 15205
 Ph: 412.429.2324 • 800.365.2324 • Fax: 412.429.2114
 www.cecinc.com

PITTSBURGH PENNSYLVANIA
 Pittsburgh Water & Sewer Authority


CITY OF PITTSBURGH
DEPARTMENT OF PUBLIC WORKS
PITTSBURGH WATER & SEWER AUTHORITY
PITTSBURGH, ALLEGHENY COUNTY, PA

DRAWN BY: LJK/KPK	CHECKED BY: KPK	APPROVED BY: KPK
DATE: OCTOBER 2019	DWG SCALE:	PROJECT NO: 18-840
EROSION AND SEDIMENT CONTROL PLAN		C900




- NOTES:**
- REMOVE TOPSOIL PRIOR TO INSTALLATION OF ROCK CONSTRUCTION ENTRANCE. EXTEND ROCK OVER FULL WIDTH OF ENTRANCE.
 - RUNOFF SHALL BE DIVERTED FROM ROADWAY TO A SUITABLE SEDIMENT REMOVAL BMP PRIOR TO ENTERING ROCK CONSTRUCTION ENTRANCE.
 - MOUNTABLE BERM SHALL BE INSTALLED WHEREVER OPTIONAL CULVERT PIPE IS USED AND PROPER PIPE COVER AS SPECIFIED BY MANUFACTURER IS NOT OTHERWISE PROVIDED. PIPE SHALL BE SIZED APPROPRIATELY FOR SIZE OF DITCH BEING CROSSED.
 - MAINTENANCE: ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE. ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE IMMEDIATELY. IF EXCESSIVE AMOUNTS OF SEDIMENT ARE BEING DEPOSITED ON ROADWAY, EXTEND LENGTH OF ROCK CONSTRUCTION ENTRANCE BY 50 FOOT INCREMENTS UNTIL CONDITION IS ALLEVIATED OR INSTALL WASH RACK, WASHING THE ROADWAY OR SWEEPING THE DEPOSITS INTO ROADWAY DITCHES, SEWERS, CULVERTS, OR OTHER DRAINAGE COURSES IS NOT ACCEPTABLE.

DETAIL 901
PADEP STANDARD CONSTRUCTION DETAIL #3-1
ROCK CONSTRUCTION ENTRANCE
NOT TO SCALE




- NOTES:**
- SEED AND SOIL AMENDMENTS SHALL BE APPLIED ACCORDING TO THE RATES IN THE PLAN DRAWINGS PRIOR TO INSTALLING THE BLANKET.
 - PROVIDE ANCHOR TRENCH AT TOE OF SLOPE IN SIMILAR FASHION AS AT TOP OF SLOPE.
 - SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS, AND GRASS.
 - BLANKET SHALL HAVE GOOD CONTINUOUS CONTACT WITH UNDERLYING SOIL THROUGHOUT ENTIRE LENGTH. LAY BLANKET LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH SOIL. DO NOT STRETCH BLANKET.
 - THE BLANKET SHALL BE STAPLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
 - BLANKETED AREAS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT UNTIL PERENNIAL VEGETATION IS ESTABLISHED TO A MINIMUM UNIFORM 70% COVERAGE THROUGHOUT THE BLANKETED AREA. DAMAGED OR DISPLACED BLANKETS SHALL BE RESTORED OR REPLACED WITHIN 4 CALENDAR DAYS.

DETAIL 904
PADEP STANDARD CONSTRUCTION DETAIL #11-1
EROSION CONTROL BLANKET INSTALLATION
NOT TO SCALE




- NOTES:**
- ACTUAL LAYOUT DETERMINED IN THE FIELD.
 - THE CONCRETE WASHOUT SIGN SHALL BE INSTALLED WITHIN 30' OF THE TEMPORARY CONCRETE WASHOUT FACILITY.

DETAIL 902
TEMPORARY CONCRETE WASHOUT FACILITY
NOT TO SCALE



- NOTES:**
- LOW VOLUME FILTER BAGS SHALL BE MADE FROM NON-WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STITCHED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS. HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE FOLLOWING STANDARDS:
- | PROPERTY | TEST METHOD | MINIMUM STANDARD |
|--------------------------|-------------|------------------|
| AVG. WIDE WIDTH STRENGTH | ASTM D-4884 | 60 LB/IN |
| GRAB TENSILE | ASTM D-4832 | 205 LB |
| PUNCTURE | ASTM D-4833 | 110 LB |
| MULLEN BURST | ASTM D-3786 | 350 PSI |
| UV RESISTANCE | ASTM D-4355 | 70% |
| AOS % RETAINED | ASTM D-4751 | 80 SIEVE |
- A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME 1/2 FULL OF SEDIMENT. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED.
 - BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA, AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS. WHERE THIS IS NOT POSSIBLE, A GEOTEXTILE UNDERLAYMENT AND FLOW PATH SHALL BE PROVIDED. BAGS MAY BE PLACED ON FILTER STONE TO INCREASE DISCHARGE CAPACITY. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5%. FOR SLOPES EXCEEDING 5%, CLEAN ROCK OR OTHER NON-ERODIBLE AND NON-POLLUTING MATERIAL MAY BE PLACED UNDER THE BAG TO REDUCE SLOPE STEEPNESS.
 - NO DOWNSLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. COMPOST BERM OR COMPOST FILTER SOCK SHALL BE INSTALLED BELOW BAGS LOCATED IN HQ OR EV WATERSHEDS, WITHIN 50 FEET OF ANY RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAILABLE.
 - THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS PURPOSE.
 - THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR 1/2 THE MAXIMUM SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHALL BE FLOATING AND SCREENED.
 - FILTER BAGS SHALL BE INSPECTED DAILY. IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE IMMEDIATELY AND NOT RESUME UNTIL THE PROBLEM IS CORRECTED.

DETAIL 905
STANDARD CONSTRUCTION DETAIL #3-16
PUMPED WATER FILTER BAG
NOT TO SCALE




- NOTES:**
- SOCK FABRIC SHALL MEET STANDARDS OF TABLE 4.1 OF THE PA DEP EROSION CONTROL MANUAL. COMPOST SHALL MEET THE STANDARDS OF TABLE 4.2 OF THE PA DEP EROSION CONTROL MANUAL.
 - COMPOST FILTER SOCK SHALL BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE BARRIER SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN BARRIER ALIGNMENT. MAXIMUM SLOPE LENGTH ABOVE ANY BARRIER SHALL NOT EXCEED THAT SPECIFIED FOR THE SIZE OF THE SOCK AND THE SLOPE OF ITS TRIBUTARY AREA.
 - TRAFFIC SHALL NOT BE PERMITTED TO CROSS COMPOST FILTER SOCKS.
 - ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES 1/2 THE ABOVE GROUND HEIGHT OF THE BARRIER AND DISPOSED IN THE MANNER DESCRIBED ELSEWHERE IN THE PLAN.
 - COMPOST FILTER SOCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24 HOURS OF INSPECTION.
 - BIODEGRADABLE COMPOST FILTER SOCKS SHALL BE REPLACED AFTER 6 MONTHS; PHOTODEGRADABLE SOCKS AFTER 1 YEAR. POLYPROPYLENE SOCKS SHALL BE REPLACED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.
 - UPON STABILIZATION OF THE AREA TRIBUTARY TO THE SOCK, STAKES SHALL BE REMOVED. THE SOCK MAY BE LEFT IN PLACE AND VEGETATED OR REMOVED. IN THE LATTER CASE, THE MESH SHALL BE CUT OPEN AND THE MULCH SPREAD AS A SOIL SUPPLEMENT.

SOCK ID	SOCK SIZE
1	18"
2	18"
3	18"

DETAIL 903
PADEP STANDARD CONSTRUCTION DETAIL #4-1
COMPOST FILTER SOCK
NOT TO SCALE

- INSTRUCTIONS**
- Before covering, make sure grate and surrounding area are free of any debris or grit so magnetic bottom can fully contact grate.
 - Lay IFM over grate. Slightly adjust to find snuggest contact of magnetic bottom.
 - Remove at least one red overflow plug if grate is at low point of street. In the event of flooding, pull the second plug to de-water the street.
 - Thoroughly clean off sediment, leaves, and other debris after every rain event.
 - Once full of sediment, IFM should be swapped out for cleaning using a garden hose or power washer.
 - If unit is run over often and beginning to compress it should be discarded.
 - In snowy regions IFM may be scraped off by plow trucks - use product accordingly.
 - Filtering fiber is compostable coconut coir; magnetics are rubber with ferrous oxide.
 - Call MKB Company at (888) 587-0777 to find the Regional Distributor in your area.



DETAIL 906
INLET FILTER MAT
NOT TO SCALE

DRAFT

PRELIMINARY
NOT FOR CONSTRUCTION

REVISION RECORD

NO	DATE	DESCRIPTION

SciTek
CONSULTANTS, INC.
1880 JOHN F. KENNEDY BLVD, SUITE 600
PHILADELPHIA, PA 19107
PHONE: (267) 341-5355 FAX: (267) 619-0273
www.scitekanswers.com

CEC
Civil & Environmental Consultants, Inc.
333 Baldwin Road - Pittsburgh, PA 15205
Ph: 412.429.2324 - 800.365.2324 - Fax: 412.429.2114
www.ccecinc.com

PITTSBURGH
PENNSYLVANIA
PGH₂O Pittsburgh Water & Sewer Authority

CITY OF PITTSBURGH
DEPARTMENT OF PUBLIC WORKS
PITTSBURGH WATER & SEWER AUTHORITY
PITTSBURGH, ALLEGHENY COUNTY, PA

DRAWN BY: LJK/KPK CHECKED BY: KPK APPROVED BY: KPK
DATE: OCTOBER 2019 DWG SCALE: PROJECT NO: 18-840
EROSION AND SEDIMENT CONTROL PLAN

DRAWING NO.: **C901**

S:\customers\2019\18-840_CEC_MRF\6_Engineering-Permitting\From CEC\CAD\Design\Files\Report\Stormwater networks grading as limits\CBS Design Drawing\178888R-C01-CE_MRF.dwg/PANNER HOLLOW C901-DETAILS LS(10/16/2019 12:07 PM) - LJK - 10/21/2019 12:07 PM

GENERAL EROSION CONTROL NOTES

1. THE LOCATION OF EXISTING UTILITIES AND UNDERGROUND STRUCTURES SHOWN ARE APPROXIMATE AND THOSE SHOWN ARE NOT NECESSARILY ALL THE EXISTING UTILITIES AND STRUCTURES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE THE EXACT LOCATION OF ALL ABOVE AND BELOW GROUND UTILITIES AND STRUCTURES PRIOR TO INITIATING CONSTRUCTION ACTIVITIES.
 2. THE CONTRACTOR SHALL CONTACT PENNSYLVANIA ONE CALL SYSTEM INC. AT (412) 242-1776 AND THE APPROPRIATE UTILITY COMPANIES AT LEAST THREE (3) DAYS PRIOR TO THE INITIATION OF EARTHMOVING AND DEMOLITION ACTIVITIES.
 3. BEFORE INITIATING ANY REVISION TO THE APPROVED EROSION AND SEDIMENT CONTROL PLAN OR REVISIONS TO OTHER PLANS WHICH MAY AFFECT THE EFFECTIVENESS OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN, THE OPERATOR MUST RECEIVE APPROVAL OF THE REVISIONS FROM THE ALLEGHENY COUNTY CONSERVATION DISTRICT (ACCD). THE OPERATOR SHALL ASSURE THAT THE APPROVED EROSION AND SEDIMENT CONTROL PLAN IS PROPERLY AND COMPLETELY IMPLEMENTED. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO ELIMINATE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION.
 4. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE EROSION AND SEDIMENT POLLUTION CONTROL PROGRAM MANUAL PREPARED BY THE PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION (DEP), BUREAU OF SOIL AND WATER CONSERVATION, LATEST EDITION.
 5. ADDITIONAL EROSION AND SEDIMENTATION CONTROL MEASURES MAY BE REQUIRED AS DEEMED NECESSARY BY THE ACCD, OWNER OR TOWNSHIP IN THE EVENT ANY UNFORESEEN PROBLEMS ARISE DURING CONSTRUCTION.
 6. THE CONTRACTOR SHALL INSTALL SOIL EROSION AND SEDIMENTATION CONTROL MEASURES PRIOR TO ANY SOIL DISTURBANCE, OR IN THEIR PROPER SEQUENCE AND MAINTAIN THEM UNTIL PERMANENT STABILIZATION IS ESTABLISHED.
 7. THE AGGREGATE BASE COURSE SHALL BE APPLIED IMMEDIATELY FOLLOWING ROUGH GRADING AND INSTALLATION OF IMPROVEMENTS IN ORDER TO STABILIZE PARKING AREAS.
 8. THE CONTRACTOR SHALL VERIFY ALL EXISTING UTILITIES TO BE REMOVED, RELOCATED AND/OR RAZED ARE DISCONNECTED PRIOR TO INITIATING EARTHMOVING ACTIVITIES.
 9. THE CONTRACTOR SHALL LANDSCAPE OR VEGETATE DISTURBED AREAS THAT WILL BE LEFT EXPOSED MORE THAN 4 DAYS, AND NOT SUBJECT TO CONSTRUCTION TRAFFIC. IF THE SEASON PREVENTS THE ESTABLISHMENT OF A TEMPORARY COVER, STRAW MULCH SHALL BE APPLIED AT A RATE OF THREE (3) TONS PER ACRE OVERTOP EXPOSED AREAS.
 10. CLEARED AND GRUBBED MATERIAL SHALL BE DISPOSED OF AT AN APPROVED WASTE SITE. BURNING SHALL NOT BE PERMITTED.
 11. AT THE TIME WHEN THE SITE PREPARATION FOR PERMANENT VEGETATIVE STABILIZATION IS GOING TO BE ACCOMPLISHED, ANY SOIL THAT WILL NOT PROVIDE A SUITABLE ENVIRONMENT TO SUPPORT ADEQUATE VEGETATIVE GROUND COVER SHALL BE REMOVED OR TREATED BY THE CONTRACTOR TO MAKE IT SUITABLE TO SUPPORT VEGETATIVE GROUND COVER.
 12. THE CONTRACTOR SHALL VEGETATE ALL EXPOSED AREAS THAT WILL NOT BE LANDSCAPED WITHIN FOUR (4) DAYS AFTER FINAL GRADING.
 13. THE CONTRACTOR SHALL CONTROL DUST WITH WATER OR OTHER METHODS APPROVED BY THE LOCAL SOIL CONSERVATION DISTRICT AND THE OWNER.
 14. THE CONTRACTOR SHALL INSTALL COMPOST FILTER SOCKS ALONG THE PERIMETER OF ALL SOIL STOCKPILES.
 15. THE CONTRACTOR SHALL INSTALL EROSION CONTROL BLANKETS OVERTOP OF 3:1 (HORIZONTAL: VERTICAL) OR STEEPER SLOPES. EROSION CONTROL BLANKETS SHALL BE NORTH AMERICAN GREEN S150BN OR APPROVED EQUAL.
 16. THE CONTRACTOR SHALL SUBMIT A PREPAREDNESS, PREVENTION AND CONTINGENCY (PPC) PLAN TO THE OWNER PRIOR TO CONSTRUCTION IF CHEMICALS, SOLVENTS OR OTHER HAZARDOUS WASTES OR MATERIALS WITH THE POTENTIAL TO CAUSE ACCIDENTAL POLLUTION DURING EARTHMOVING OR OTHER CONSTRUCTION ACTIVITIES ARE STORED OR USED ON SITE. THE PPC PLAN SHALL BE PREPARED IN ACCORDANCE WITH "GUIDELINES FOR THE DEVELOPMENT AND IMPLEMENTATION OF PREPAREDNESS, PREVENTION AND CONTINGENCY (PPC) PLANS", PREPARED BY PAPER BUREAU OF SOIL AND WATER MANAGEMENT AND PAPER BUREAU OF WATER QUALITY MANAGEMENT.
 17. THE CONTRACTOR SHALL CONSTRUCT A BERM AROUND AREAS WHERE HYDRAULIC FLUID AND DIESEL FUEL WILL BE STORED DURING CONSTRUCTION TO SERVE AS A CONTAINMENT AREA FOR THE CONTROL OF POSSIBLE SPILLS. ANY SPILL WITHIN THE CONTAINMENT AREA SHALL BE IMMEDIATELY CLEANED. TELEPHONE NUMBERS OF EMERGENCY RESPONSE TEAMS ARE TO BE KEPT ON SITE, AND THEY ARE TO BE NOTIFIED IN THE CASE OF A SPILL.
 18. THE CONTRACTOR SHALL REFER TO OTHER PLANS WITHIN THIS CONSTRUCTION SET FOR OTHER PERTINENT INFORMATION.
 19. THE CONTRACTOR SHALL PROVIDE THE LOCATION AND ANY APPLICABLE PERMIT NUMBERS OF ALL THE OFF SITE DISPOSAL AND BORROW SITES THAT WILL BE UTILIZED DURING CONSTRUCTION TO THE ACCD PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL ALSO IDENTIFY THE EROSION AND SEDIMENTATION CONTROL MEASURES, WHICH WILL BE IMPLEMENTED AT THE DISPOSAL AND/OR BORROW SITES. IF THE DISPOSAL AND/OR BORROW SITES ARE UNPERMITTED, AN EROSION AND SEDIMENTATION PLAN MUST BE APPROVED BY THE ACCD PRIOR TO THEIR USE.
 20. RUNOFF DRAINS INTO DOWNSTREAM TO JUNCTION HOLLOW.
 21. UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENTATION BMPs MUST BE MAINTAINED PROPERLY. MAINTENANCE MUST INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENTATION BMPs AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL SITE INSPECTIONS WILL BE DOCUMENTED IN AN INSPECTION LOG KEPT FOR THIS PURPOSE. THE COMPLIANCE ACTIONS AND THE DATE, TIME AND NAME OF THE PERSON CONDUCTING THE INSPECTION. THE INSPECTION LOG WILL BE KEPT ONSITE AT ALL TIMES AND MADE AVAILABLE TO THE ACCD UPON REQUEST.
 22. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING AND RENITING, MUST BE PERFORMED IMMEDIATELY. IF EROSION AND SEDIMENTATION BMPs FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMPs OR MODIFICATIONS OF THOSE INSTALLED WILL BE NEEDED.
 23. WHERE BMPs ARE FOUND TO FAIL TO ALLEVIATE EROSION OR SEDIMENT POLLUTION, THE PERMITTEE OR CO-PERMITTEE SHALL INCLUDE THE FOLLOWING INFORMATION:
 - A. THE LOCATION AND SEVERITY OF THE BMP'S FAILURE AND ANY POLLUTION EVENTS.
 - B. ALL STEPS TAKEN TO REDUCE, ELIMINATE AND PREVENT THE RECURRENT OF THE NON-COMPLIANCE.
 - C. THE TIME FRAME TO CORRECT THE NON-COMPLIANCE, INCLUDING THE EXACT DATES WHEN THE ACTIVITY WILL RETURN TO COMPLIANCE.
 24. AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENT BMPs MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL OF THE BMPs MUST BE STABILIZED IMMEDIATELY.
 25. THE CONTRACTOR IS ADVISED TO BECOME THOROUGHLY FAMILIAR WITH THE PROVISIONS OF THE APPENDIX 64, EROSION CONTROL NOTES, RULES AND REGULATIONS, TITLE 25, PART 1, DEPARTMENT OF ENVIRONMENTAL PROTECTION, SUBPART C, PROTECTION OF NATURAL RESOURCES, ARTICLE III, WATER RESOURCES, CHAPTER 102, EROSION CONTROL.
 26. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES. THE OPERATOR SHALL ASSURE THAT AN EROSION AND SEDIMENT CONTROL PLAN HAS BEEN PREPARED, APPROVED BY THE ACCD, AND IS BEING IMPLEMENTED AND MAINTAINED THROUGHOUT ALL SOIL AND/OR ROCK SOIL AND BORROW AREAS, REGARDLESS OF LOCATION.
 27. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM UNIFORM 70% PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING AND OTHER MOVEMENTS. IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE, THE OPERATOR SHALL STABILIZE ANY AREAS DISTURBED BY THE ACTIVITIES. DURING NON-GERMINATING PERIODS, MULCH MUST BE APPLIED AT THE SPECIFIED RATES. DISTURBED AREAS WHICH ARE NOT AT FINISHED GRADE AND WHICH WILL BE REDISTRIBUTED WITHIN 1 YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE STABILIZATION SPECIFICATIONS. DISTURBED AREAS WHICH ARE AT FINISHED GRADE OR WHICH WILL NOT BE REDISTRIBUTED WITHIN 1 YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE PERMANENT VEGETATIVE STABILIZATION SPECIFICATIONS.
 28. THE RESPONSIBILITY FOR PERFORMING ENVIRONMENTAL DUE DILIGENCE AND THE DETERMINATION OF CLEAN FILL RESIDES WITH THE OPERATOR.
 29. PROCEDURES WHICH ENSURE THAT THE PROPER MEASURES FOR THE RECYCLING OR DISPOSAL OF MATERIALS ASSOCIATED WITH OR FROM THE PROJECT SITE WILL BE UNDERTAKEN IN ACCORDANCE WITH THE PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTIONS, TITLE 25, CHAPTER 102.4 #5 SECTION XI.
 30. A LICENSED PROFESSIONAL OR THEIR DESIGNEE SHALL BE PRESENT ON THE PROJECT SITE DURING THE CONSTRUCTION OF ALL BMPs.
- CLEAN FILL IS DEFINED AS: UNCONTAMINATED, NON-WATER SOLUBLE, NON-DECOMPOSABLE, INERT, SOLID MATERIAL. THE TERM INCLUDES SOIL, ROCK, STONE, DREKED MATERIAL, USED ASPHALT, AND BRICK, BLOCK OR CONCRETE FROM CONSTRUCTION AND DEMOLITION ACTIVITIES THAT IS SEPARATE FROM OTHER WASTE AND IS RECOGNIZABLE AS SUCH. THE TERM DOES NOT INCLUDE MATERIALS PLACED IN OR ON THE WATERS OF THE COMMONWEALTH UNLESS OTHERWISE AUTHORIZED. (THE TERM "USED ASPHALT" DOES NOT INCLUDE MILLED ASPHALT OR ASPHALT THAT HAS BEEN PROCESSED FOR RE-USE.)
- CLEAN FILL AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE: FILL MATERIALS AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE STILL QUALIFY AS CLEAN FILL PROVIDED THE TESTING REVEALS THAT THE FILL MATERIAL CONTAINS CONCENTRATIONS OF REGULATED SUBSTANCES THAT ARE BELOW THE RESIDENTIAL LIMITS IN TABLES FP-1A AND FP-1B FOUND IN THE DEPARTMENT'S POLICY "MANAGEMENT OF FILL".
- ANY PERSON PLACING CLEAN FILL THAT HAS BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE MUST USE FORM FP-001 TO CERTIFY THE ORIGIN OF THE FILL MATERIAL AND THE RESULTS OF THE ANALYTICAL TESTING TO QUALIFY THE MATERIAL AS CLEAN FILL. FORM FP-001 MUST BE RETAINED BY THE OWNER OF THE PROPERTY RECEIVING THE FILL. A COPY OF FORM FP-001 CAN BE FOUND AT THE END OF THESE INSTRUCTIONS.
- ENVIRONMENTAL DUE DILIGENCE, INVESTIGATIVE TECHNIQUES, INCLUDING, BUT NOT LIMITED TO, VISUAL PROPERTY INSPECTIONS, ELECTRONIC DATA BASE SEARCHES, REVIEW OF PROPERTY OWNERSHIP, REVIEW OF PROPERTY USE HISTORY, SANBORN MAPS, ENVIRONMENTAL QUESTIONNAIRES, TRANSACTION SCREENS, ANALYTICAL TESTING, ENVIRONMENTAL ASSESSMENTS OR AUDITS. ANALYTICAL TESTING IS NOT A REQUIRED PART OF DUE DILIGENCE UNLESS VISUAL INSPECTION AND/OR REVIEW OF THE PAST LAND USE OF THE PROPERTY INDICATES THAT THE FILL MAY HAVE BEEN SUBJECTED TO A SPILL OR RELEASE OF REGULATED SUBSTANCE. IF THE FILL MAY HAVE BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE, IT MUST BE TESTED TO DETERMINE IF IT QUALIFIES AS CLEAN FILL. TESTING SHOULD BE PERFORMED IN ACCORDANCE WITH APPENDIX A OF THE DEPARTMENT'S POLICY "MANAGEMENT OF FILL".
- FILL MATERIAL THAT DOES NOT QUALIFY AS CLEAN FILL IS REGULATED FILL. REGULATED FILL IS WASTE AND MUST BE MANAGED IN ACCORDANCE WITH THE DEPARTMENT'S MUNICIPAL OR RESIDUAL WASTE REGULATIONS BASED ON 25 PA. CODE CHAPTERS 287 RESIDUAL WASTE MANAGEMENT OR 271 MUNICIPAL WASTE MANAGEMENT, WHICHEVER IS APPLICABLE.

TEMPORARY CONTROL MEASURES

- THE E&S CONTROL FACILITIES PROPOSED FOR THE PROPOSED PANTHER HOLLOW LAKE PROJECT ARE SHOWN ON THE E&S CONTROL PLAN. CONTROL MEASURES SHOWN ON THIS PLAN ARE MINIMUM CONTROLS TO REDUCE THE POTENTIAL FOR OFFSITE AREAS TO RECEIVE SEDIMENT-LADEN RUNOFF. ADDITIONAL CONTROLS MAY BE REQUIRED DEPENDING ON THE PROGRESS OF CONSTRUCTION AND VARYING CONDITIONS ENCOUNTERED.
1. ROCK CONSTRUCTION ENTRANCE

ROCK CONSTRUCTION ENTRANCES WILL BE PROVIDED AT THE LOCATIONS SHOWN ON THE PLANS AND IN ACCORDANCE WITH THE STANDARD DETAIL.

INSTALLATION: TO CONSTRUCT THE PAD, PLACE A LAYER OF GEOTEXTILE AND AN INITIAL 2 TO 3 INCHES OF STONE ACROSS THE FULL WIDTH OF THE VEHICLE INGRESS AND EGRESS AREA. THE STONE PAD SHOULD BE AT LEAST 50 FEET IN LENGTH, 20 FEET IN WIDTH, AND 8 INCHES THICK. COMPLETE THE PLACEMENT OF STONE TO THE REQUIRED THICKNESS.
 2. SILT SOCK

SILT SOCK SHALL BE INSTALLED IN THE LOCATIONS SHOWN ON THE PLANS AND IN ACCORDANCE WITH THE STANDARD DETAIL PROVIDED. VARIOUS FILTER SOCK SIZES SHALL BE INSTALLED, AS INDICATED, AT THE LOCATIONS SHOWN ON THE PLANS AND IN ACCORDANCE WITH THE STANDARD DETAILS PROVIDED.

INSTALLATION:

 1. SILT SOCK SHALL BE INSTALLED PARALLEL TO THE BASE OF THE SLOPE OR OTHER DISTURBED AREA, PERPENDICULAR TO SHEET FLOW.
 2. STAKES SHALL BE INSTALLED THROUGH THE MIDDLE OF THE SILT SOCK ON 10 FT. CENTERS, USING 2-INCH BY 2-INCH BY 3-FOOT WOODEN STAKES.
 3. STAKING DEPTH FOR SAND AND SILT LOAM SOILS SHALL BE 12-INCH, AND 8-INCH FOR CLAY SOILS.
 4. LOOSE COMPOST MAY BE BACKFILLED ALONG THE UPSLOPE SIDE OF THE SILT SOCK, FILLING THE SEAM BETWEEN THE SOIL SURFACE AND THE DEVICE, IMPROVING FILTRATION AND SEDIMENT RETENTION.

MAINTENANCE:

 1. SILT SOCKS SHOULD BE REGULARLY INSPECTED TO MAKE SURE THEY HOLD THEIR SHAPE AND ARE PRODUCING ADEQUATE FLOW THROUGH.
 2. IF PONDING BECOMES EXCESSIVE, AND SEDIMENT REACHES THE TOP OF THE FILTER SOCK, ADDITIONAL FILTER SOCKS SHOULD BE ADDED IN THE AREAS WITHOUT DISTURBANCE OF SOIL OR COLLECTED SEDIMENT.

WHEN CONSTRUCTION IS COMPLETED ON SITE, THE SILT SOCKS MAY BE DISPERSED WITH A LOADER, RAKE, BULLDOZER OR OTHER DEVICE TO BE INCORPORATED IN THE SOIL OR LEFT ON TOP OF THE SOIL FOR FINAL SEEDING TO OCCUR. THE MESH NETTING MATERIAL SHALL BE COLLECTED AND DISPOSED OF IN A NORMAL TRASH CONTAINER OR REMOVED BY THE CONTRACTOR. IN CASES WHERE BIODEGRADABLE OR PHOTODEGRADABLE PRODUCTS ARE USED, THEY MAY BE LEFT ONSITE AT THE DIRECTION OF THE OWNER.
 3. TEMPORARY VEGETATIVE STABILIZATION

INSTALLATION: FERTILIZING, SEEDING, AND MULCHING WILL BE USED AS A TEMPORARY E&S CONTROL MEASURE ON ALL NON-PAVED DISTURBED AREAS. EXPOSED SOILS NOT SUBJECT TO CONSTRUCTION TRAFFIC SHALL NOT REMAIN UNSEEDED OR COVERED BY MULCH FOR MORE THAN 4 DAYS, INCLUDING STOCKPILED SOIL MATERIALS. WITH REGARD TO THE TEMPORARY SEED MIX, REFER TO THE SEEDING MIXTURE TABLE PROVIDED ON THE E&S CONTROL PLAN DETAIL SHEET.

WHERE SLOPES PERMIT, PROMPTLY DISK ALL AMENDMENTS UNDER A 3- TO 6-INCH DEPTH. WHERE SLOPES DO NOT PERMIT TILLAGE, TRACK SLOPE WITH A DOZER AS DESCRIBED UNDER SEEDBED PREPARATION. ON EXTREMELY STEEP SLOPES, AMENDMENTS MAY BE APPLIED WITH THE SEED AND MULCH USING A HYDROSEEDER AS LONG AS SEED AND INOCULANT IS NOT IN A SLURRY WITH FERTILIZERS FOR MORE THAN ONE HOUR.

PREPARE SEEDBED BY CULTIPACKING OR TRACKING WITH A DOZER USING EQUIPMENT (SUCH AS A LIGHT TRACTOR) AND TECHNIQUES THAT MINIMIZE RUTTING OF THE SURFACE. IF TRACKING IS DONE, RUN DOZER SO TRACK MARKS ARE PARALLEL TO SITE CONTOURS. IF A BRILLION SEEDER IS USED, THIS STEP MAY BE SKIPPED.

JUST BEFORE SEEDING, INOCULATE BIRDSFOOT TREFLOID SEED (WHEN APPLICABLE) WITH LEGUME INOCULANT APPROPRIATE FOR BIRDSFOOT TREFLOID. USING AT LEAST FIVE TIMES THE MANUFACTURER'S MINIMUM INOCULANT APPLICATION RATES, THEN EVENLY APPLY THE APPROPRIATE SEED MIXTURE.

LIGHTLY CULTIPACK TO PRESS SEED INTO SEEDBED USING EQUIPMENT (SUCH AS A LIGHT TRACTOR) AND TECHNIQUE THAT MINIMIZES RUTTING OF THE SURFACE. IF A BRILLION SEEDER IS USED, THIS STEP MAY BE CONSIDERED COMPLETE. IF SLOPES ARE TOO STEEP TO PERMIT SEED PREPARATION AND PLACEMENT, USE HYDROSEEDING TECHNIQUES.

PROMPTLY AND EVENLY APPLY STRAW (NOT HAY) MULCH AT A RATE OF 3 TONS PER ACRE USING A BALE-BUSTER OR USING WOOD CELLULOSE FIBER (NOT PAPER PULP) HYDROMULCH AT A RATE OF 3,000 POUNDS PER ACRE. PROMPTLY TACK STRAW INTO PLACE USING ONE OF THE FOLLOWING METHODS: 1) APPLY "HYDRORAM" (LINEAR POLYACRYLAMIDE POLYMER) DISTRIBUTED BY POLYMERS, INC. (WWW.WATERSORB.COM OR 501-623-9995) WITH WATER OVER STRAW AT A RATE OF 8 POUNDS PER ACRE; 2) APPLY 800 TO 1,000 POUNDS PER ACRE APPLICATION OF WOOD CELLULOSE FIBER MULCH WITH A HYDROSEEDER OVER THE STRAW; OR 3) USE A CRIMPER DISK (A SPECIALLY DESIGNED HEAVY DISK WITH NO OFFSET TO THE DIRECTION OF TRAVEL). MAKE MULTIPLE PASSES WITH THE CRIMPER AS NECESSARY TO SECURE THE STRAW.
 4. INLET PROTECTION

INLET PROTECTION FILTERS CONSISTING OF INLET FILTER BAGS OR STONE AND GRAVEL WILL BE PROVIDED AT ALL STORM SEWER INLETS AS THEY ARE INSTALLED TO FILTER SEDIMENT-LADEN WATER PRIOR TO ENTERING THE STORM SEWER SYSTEM.

INSTALLATION: THE INLET PROTECTION FILTERS SHALL BE INSTALLED IN THE LOCATIONS SHOWN ON THE PLAN AND IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
 5. TOPSOIL STOCKPILE AREA

INSTALLATION: THERE WILL BE A DESIGNATED TOPSOIL STOCKPILE AREA LOCATED ON THE PROPERTY. THE LOCATION SHALL BE AS SHOWN ON THE E&S SITE PLANS AND ALL TOPSOIL AND EXCESS CUT MATERIAL FROM THE SITE SHALL BE STOCKPILED THERE. THE STOCKPILE WILL BE SURROUNDED WITH A MINIMUM 18" SILT SOCK TO PREVENT SEDIMENT-LADEN RUNOFF.
 6. EROSION CONTROL BLANKET

THE NORTH AMERICAN GREEN S150BN EROSION CONTROL BLANKET, OR AN APPROVED EQUAL, SHALL BE INSTALLED ON ALL SLOPES 3:1 OR STEEPER.

INSTALLATION: INSTALL IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
 7. CONSTRUCTION WASTE RECYCLING/DISPOSAL

CONSTRUCTION WASTES ARE REFUSE MATERIALS GENERATED DURING THE COURSE OF CONSTRUCTION AND INCLUDE, BUT ARE NOT LIMITED TO, PAPER, PLASTIC, WOOD, FOOD, TEXTILE, AND METAL PRODUCTS.

INSTALLATION: THE CONTRACTOR SHALL BE RESPONSIBLE FOR IDENTIFYING WASTE RECYCLING/DISPOSAL AREAS ON THE EROSION AND SEDIMENT CONTROL PLANS ONCE THEY HAVE BEEN DETERMINED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL WASTE RECYCLING/DISPOSAL PERMITS PRIOR TO THE COMMENCEMENT OF CONSTRUCTION ACTIVITIES.

MAINTENANCE: ALL CONSTRUCTION WASTE SHALL BE REMOVED BY THE CONTRACTOR AND DISPOSED OF AT A STATE APPROVED WASTE SITE AND IN ACCORDANCE WITH ALL LOCAL AND STATE CODES AND PERMIT REQUIREMENTS. THE BURNING OF WASTE MATERIALS SHALL NOT BE PERMITTED.

TEMPORARY CONTROL MEASURES

10. SILT FILTER BAG

FILTER BAGS MAY BE USED, IF NECESSARY, TO PREVENT SEDIMENT LADEN WATER THAT MAY BE PUMPED FROM TRENCHES FROM DISCHARGING INTO WETLANDS AND STREAMS OR OFFSITE. THEY SHALL BE MADE FROM NON-WOVEN GEOTEXTILE MATERIAL AND SHALL TRAP PARTICLES LARGER THAN 150 MICRONS. PUMPING RATES SHALL NOT EXCEED ONE-HALF MANUFACTURER'S SPECIFICATIONS, OR 750 GPM, WHICHEVER IS LESS. THE FOLLOWING INSTRUCTIONS SHALL SPECIFY CONDITIONS FOR ITS USE.

INSTALLATION:

 1. INSTALL BAGS ON A WELL-VEGETATED, EROSION-RESISTANT AREA.
 2. BAGS SHALL NOT BE PLACED ON A SLOPE GREATER THAN 5%.
 3. BAGS MUST BE PLACED ON A DRY AREA, AWAY FROM STREAMS AND WETLANDS.
 4. PUMP INTAKES SHOULD BE FLOATING AND SCREENED.

MAINTENANCE:

 1. FILTER BAGS SHALL BE INSPECTED DAILY. IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE UNTIL THE PROBLEM IS CORRECTED.
 2. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME HALF FULL.
 3. A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES MUST BE PROVIDED.
 4. SPARE BAGS SHALL BE KEPT AVAILABLE ONSITE.
 5. ALL CLEAN OUT MATERIAL SHALL BE DISCARDED IN AN UPLAND AREA, REMOTE OF ANY STREAM OR WETLAND, WITHIN THE CONSTRUCTION RIGHT-OF-WAY. ALL AREAS WILL BE STABILIZED.
11. CONCRETE WASHOUT

CONCRETE WASHOUTS SHALL BE CONSTRUCTED ONSITE TO CONTAIN ALL WASHOUT WATER FROM CONCRETE CONSTRUCTION ACTIVITIES. WASHOUTS SHALL BE CLEARLY MARKED.

INSTALLATION: WASHOUTS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE STANDARD DETAIL PROVIDED.

MAINTENANCE: WASHOUTS SHALL BE CLEANED OUT WHEN ACCUMULATED MATERIALS TAKE UP TWO-THIRDS OF THE AVAILABLE STORAGE CAPACITY. MATERIALS SHALL BE DISPOSED OF IN A PADEP-APPROVED FACILITY. MAKE ANY REPAIRS TO THE CONTAINMENT FACILITY AS NEEDED.
12. TRENCH PLUGS

TRENCH PLUGS SHALL BE INSTALLED AS NEEDED DURING ALL TRENCHING ACTIVITIES, IN ACCORDANCE WITH THE STANDARD DETAILS.

INSTALLATION:

 1. PIPELINES WITH JOINTS THAT ALLOW A MANUFACTURED LENGTH OF PIPE TO BE PLACED IN THE TRENCH WITH THE PIPE JOINT ASSEMBLED IN THE TRENCH REQUIRE AN OPEN TRENCH THAT IS ONLY SLIGHTLY LONGER THAN THE LENGTH OF PIPE BEING INSTALLED.
 2. THE TOTAL LENGTH OF EXCAVATED TRENCH OPEN AT ANY ONE TIME SHOULD NOT BE GREATER THAN THE TOTAL LENGTH OF PIPELINE/UTILITY LINE THAT CAN BE PLACED IN THE TRENCH AND BACKFILLED IN ONE WORKING DAY.
 3. NO MORE THAN 50 FEET OF OPEN TRENCH SHOULD EXIST WHEN PIPELINE/UTILITY LINE INSTALLATION CEASED AT THE END OF THE WORKDAY.
 4. TRENCH PLUGS ARE REQUIRED AT ALL WATER-BODY CROSSINGS REGARDLESS OF TRENCH SLOPE.
 5. TOPSOIL MAY NOT BE USED TO FILL SACKS.
13. OUTLET PROTECTION

INSTALLATION: OUTLET PROTECTION WILL BE INSTALLED AT THE LOCATIONS SHOWN ON THE PLANS AND IN ACCORDANCE WITH STANDARD DETAIL TO PREVENT SCOUR FROM EXCESSIVE VELOCITIES.

MAINTENANCE: ADDITIONAL STONE MAY HAVE TO BE ADDED PERIODICALLY TO MAINTAIN THE PROPER FUNCTIONING OF THE APRON.

**STANDARD E&S WORKSHEET # 21
Temporary and Permanent Vegetative Stabilization Specifications**

PROJECT NAME: Four Mile Run - Panther Hollow Lake
 LOCATION: City of Pittsburgh, Allegheny County, PA
 PREPARED BY: LJK DATE: 10/17/2019
 CHECKED BY: KPK DATE: 10/17/2019
 SPECIFICATIONS: The Department recommends the use of the Penn State publication, "Erosion Control and Conservation Plantings on Noncropland," as the standard to use for the selection of species, seed specifications, mixtures, liming and fertilizing, time of seeding, and seeding methods. Specifications for these items may also be obtained from PennDOT's Publication # 408, Section 804 or by contacting the applicable county conservation district. Upon selection of a reference, that reference should be used to provide all specifications for seeding, mulching, and soil amendments. The following specification will be used for this project:

(TEMPORARY)	*SPECIES:	ANNUAL RYE (PENNDOT FORMULA)	
	% PURE LIVE SEED:	98%	%
	APPLICATION RATE:	100	LB./ACRE
	FERTILIZER TYPE:	10-20-20	LB./ACRE (X-X-X)
	FERTILIZER APPL. RATE:	680	LB./ACRE
	LIMING RATE:	6.0	T./ACRE
	MULCH TYPE:	STRAW	
	MULCHING RATE:	3.0	T./ACRE

(PERMANENT)	TOPSOIL PLACEMENT DEPTH:	8"	IN.
	*SPECIES:	20% PERENIAL RYE, 50% KENTUCKY BLUE, 30% CREEPING RED FESQUE	
	% PURE LIVE SEED:	98%	%
	APPLICATION RATE:	200	LB./ACRE
	FERTILIZER TYPE:	10-20-20	LB./ACRE (X-X-X)
	FERTILIZER APPL. RATE:	680	LB./ACRE
	LIMING RATE:	6.0	T./ACRE
	MULCH TYPE:	STRAW	
	MULCHING RATE:	3.0	T./ACRE
	ANCHOR MATERIAL:	N/A	
	ANCHORING METHOD:	N/A	
	RATE OF ANCHOR MATERIAL APPL.:	N/A	LB./ACRE
	SEEDING SEASON DATES:	MARCH 15 - JUNE 1 / AUG 1 - OCT 15	

(PERMANENT - STEEP SLOPE)	TOPSOIL PLACEMENT DEPTH:	6"	IN.
	*SPECIES:	30% ANNUAL RYE, 50% KENTUCKY 91-TALL FESQUE, 15% WHITE CLOVER, 1% CLIMAX TIMOTHY, 1% REPTID	
	% PURE LIVE SEED:	98%	%
	APPLICATION RATE:	200	LB./ACRE
	FERTILIZER TYPE:	10-20-20	LB./ACRE (X-X-X)
	FERTILIZER APPL. RATE:	680	LB./ACRE
	LIMING RATE:	6.0	T./ACRE
	MULCH TYPE:	STRAW	
	MULCHING RATE:	3.0	T./ACRE
	ANCHOR MATERIAL:	NORTH AMERICAN GREEN S150	STRAW BLANKET
	ANCHORING METHOD:	PER MANUFACTURERS SPECIFICATIONS	
	RATE OF ANCHOR MATERIAL APPL.:	PER MANUFACTURERS SPECIFICATIONS	LB./ACRE
	SEEDING SEASON DATES:	MARCH 15 - JUNE 1 / AUG 1 - OCT 15	

*If more than one species is used, indicate application rate for each species.
Note: This worksheet should be added to the plan drawings.

DRAFT

**PRELIMINARY
NOT FOR CONSTRUCTION**

REVISION RECORD		
NO	DATE	DESCRIPTION



**CITY OF PITTSBURGH
DEPARTMENT OF PUBLIC WORKS
PITTSBURGH WATER & SEWER AUTHORITY
PITTSBURGH, ALLEGHENY COUNTY, PA**

DRAWN BY: LJK/KPK	CHECKED BY: KPK	APPROVED BY: KPK
DATE: OCTOBER 2019	DWG SCALE:	PROJECT NO: 18-840
DRAWING NO.:		

**EROSION AND SEDIMENT
CONTROL PLAN**

C902

TEMPORARY/PERMANENT VEGETATIVE STABILIZATION

INSTALLATION: FERTILIZING, SEEDING, AND MULCHING WILL BE USED AS A TEMPORARY/PERMANENT E&S CONTROL MEASURE ON ALL NON-PAVED DISTURBED AREAS. EXPOSED SOILS, NOT SUBJECT TO CONSTRUCTION TRAFFIC, SHALL NOT REMAIN UNSEED OR UNCOVERED BY MULCH FOR MORE THAN 4 DAYS, INCLUDING STOCKPILED SOIL MATERIALS. WITH REGARD TO THE TEMPORARY/PERMANENT SEED MIXES, REFER TO THE SEEDING MIXTURE TABLES PROVIDED. UNLESS THE OWNER'S REPRESENTATIVE DIRECTS OTHERWISE, VEGETATION SHALL BE ESTABLISHED AS FOLLOWS:

- SOIL PLACEMENT: SOIL SHALL BE PLACED TO THE DESIGN THICKNESS AND GRADE AND TRACKED AND ROLLED INTO PLACE IN A MANNER THAT WILL NOT CAUSE EXCESSIVE COMPACTION. IF SOIL DENSITY IS VERIFIED IN THE FIELD, SOIL SHALL BE COMPACTED TO A DRY DENSITY BETWEEN 75 AND 100 POUNDS PER CUBIC FOOT, AFTER CORRECTION TO ZERO PERCENT COARSE FRAGMENT (PARTICLES LARGER THAN 2 MILLIMETERS) CONTENT.
- SOIL TESTING AND SOIL AMENDMENT (LIME AND FERTILIZER) RATES: UNLESS SOIL TEST RESULTS AND RECOMMENDATIONS FROM THE STATE AGRICULTURAL EXTENSION SERVICE LABORATORY (PENN STATE AGRICULTURAL ANALYTICAL SERVICES LABORATORY [814-863-0841] OR EQUIVALENT SOIL TESTING LABORATORY) INDICATE OTHERWISE, EVENLY APPLY: 1) AGRICULTURAL GRADE GROUND LIMESTONE AT A RATE OF 6 TONS PER ACRE (CALCIUM CARBONATE EQUIVALENT BASIS); 2) FERTILIZERS TO SUPPLY 100-200-200 POUNDS PER ACRE N-P205-K20 (EXAMPLE: 10-20-20 FERTILIZER AT A RATE OF 1000 POUNDS PER ACRE); AND, 3) "BIOPAK" MICROBIAL SOIL INOCULANT (DISTRIBUTED BY PLANT HEALTH CARE, INC. [WWW.PLANTHEALTHCARE.COM OR 800-421-9051]). IF APPROVED PASTEURIZED PELLETED POULTRY MANURE (PASTEURIZED PPM) WITH AN ANALYSIS OF AT LEAST 4-2-3 (PERCENT N-P205-K20) IS USED, IT WILL BE ASSUMED THAT ONE TON MANURE WILL SUBSTITUTE FOR 60-40-60 POUNDS N-P205-K20 AVAILABLE IN THE FIRST YEAR. A PRE-APPROVED SOURCE OF PASTEURIZED PPM IS "MICRO-START60" AS MANUFACTURED BY PERDUE AGRICULTURE, LLC (WWW.MICROSTART60.COM <HTTP://WWW.MICROSTART60.COM> OR 302-628-2360).
- SOIL AMENDMENT INCORPORATION: PROMPTLY TILL UNDER THE LIME AND FERTILIZER TO A DEPTH OF 2 TO 4 INCHES USING A DISK, HARROW, FLOW, ROTOTILLER OR OTHER SUITABLE EQUIPMENT. IF LIME REQUIREMENTS ARE LESS THAN 4 TONS PER ACRE OR SLOPES ARE TOO STEEP TO PERMIT SAFE TILLAGE, THE SOIL AMENDMENTS CAN BE MIXED INTO A HYDROMULCH SLURRY OR CAN BE TRACKED IN WITH A DOZER IN LIEU OF INCORPORATION. IF TRACKING THE SITE WITH A DOZER, TRACK IN A MANNER THAT LEAVES CLEAT MARKS PARALLEL TO SITE CONTOURS.
- TEMPORARY SEEDING THAT WILL NOT BE FOLLOWED BY PERMANENT SEEDING, SUCH AS TOPSOIL STOCKPILES OR INTERIM GRADING PATTERNS, DO NOT REQUIRE THE APPLICATION OF SLOW RELEASE FERTILIZER OR "BIOPAK" INOCULANT.
- SEEDBED PREPARATION: JUST BEFORE SEEDING, PREPARE SEEDBED BY TRACKING, RAKING, OR OTHER APPROPRIATE METHOD AS NECESSARY TO BREAK UP SOIL CRUSTS. IF TRACKING THE SITE WITH A DOZER, TRACK IN A MANNER THAT LEAVES CLEAT MARKS PARALLEL TO SITE CONTOURS.
- SEEDING: EVENLY APPLY THE TEMPORARY/PERMANENT SEED MIXTURES USING HYDROSEEDING, BROADCAST, OR DRILL SEEDING METHODS THAT PLANT SEED LESS THAN 1/4-INCH BELOW THE GROUND SURFACE. APPLY LEGUME SEED INOCULANTS SPECIFICALLY MADE FOR THE LEGUME SEED TYPE BEING APPLIED AT FIVE TIMES THE MANUFACTURER'S RECOMMENDED RATE. USE NO SEED OR INOCULANT THAT HAS BEEN IMPROPERLY STORED, EXPIRED, OR SEED OLDER THAN 9 MONTHS FROM THE SEED TEST DATE. IF HYDROSEEDING METHODS ARE USED, SEED, INOCULANTS, FERTILIZERS, AND POLYMER TACKLER/SOIL STABILIZER (GELW) MAY BE APPLIED IN ONE APPLICATION, PROVIDED THAT SEED AND INOCULANTS ARE NOT HELD IN A SLURRY WITH FERTILIZERS FOR MORE THAN ONE HOUR.
- MULCHING AND TACKING: PROMPTLY AFTER SEEDING, MULCH USING EITHER: 1) "CURLX" OR EQUIVALENT BRAND OF WOOD EXCLESIOR EROSION CONTROL BLANKET; 2) SYNTHETIC INDUSTRIES "TRM 450" OR NORTH AMERICAN GREEN "P-300" TURF REINFORCEMENT MAT; 3) STRAW APPLIED AT A RATE OF 6000 POUNDS PER ACRE, OR 4) WOOD/CELLULOSE FIBER HYDROMULCH APPLIED WITH A HYDROSEEDER AT A RATE OF 3000 POUNDS PER ACRE. WOOD/CELLULOSE FIBER HYDROMULCH MUST CONTAIN AT LEAST 50% VIRGIN WOOD FIBER. IF AT LEAST 1000 POUNDS PER ACRE APPROVED PASTEURIZED PPM IS BEING APPLIED WITH A HYDROSEEDER, WOOD/CELLULOSE FIBER HYDROMULCH RATES MAY BE REDUCED TO 2500 POUNDS PER ACRE.

IN SOME LOCATIONS SHOWN ON THE DRAWINGS, SUCH AS SLOPES STEEPER THAN 3:1 (H:V), EROSION CONTROL BLANKET OR TURF REINFORCEMENT MAT (TRM) MAY BE THE ONLY PERMISSIBLE MULCHING OPTION. INSTALL EROSION CONTROL BLANKETS/TRM PER MANUFACTURER'S INSTRUCTIONS. STAPLE BLANKET/TRM IN PLACE USING 6-INCH (MINIMUM) SOD STAPLES IN ROWS AT THE EDGES AND CENTERLINE OF THE BLANKET AND ON 24-INCH OR CLOSER CENTERS.

TACK STRAW IN PLACE USING EITHER: 1) A CRIMPER DISK, 2) WOOD/CELLULOSE FIBER HYDROMULCH APPLIED OVER THE STRAW AT A RATE OF 800-1000 POUNDS PER ACRE, OR, 3) WATER SOLUBLE LINEAR POLYACRYLATE (SODIUM ACRYLATE/ACRYLAMIDE) COPOLYMER "POLYMER" AT A RATE OF AT LEAST 8 POUNDS PER ACRE APPLIED IN MIXTURE WITH WATER OVER THE STRAW. APPROVED POLYMER BRANDS INCLUDE "WATERSORB TM PAM" OR "HYDROFAM TM", DISTRIBUTED BY POLYMERS, INC. (WWW.WATERSORB.COM OR 501-623-9995), "TERRAPAM TM", DISTRIBUTED BY PLANT HEALTH CARE, INC. (WWW.PLANTHEALTHCARE.COM OR 800-421-9051), AND "HYDROGEL BTM", DISTRIBUTED BY FINN CORPORATION (WWW.FINNCORP.COM OR 800-543-7166).

TACK WOOD/CELLULOSE FIBER HYDROMULCH IN PLACE USING "POLYMER" SPECIFIED ABOVE AT A RATE OF AT LEAST 4 POUNDS PER ACRE APPLIED IN A SLURRY WITH THE HYDROMULCH.

OVER-SEEDING AND RE-SEEDING: WHEN THE SITE DEVELOPMENT STAGING OR SEASON WILL NOT PERMIT TIMELY SOWING OF THE PERMANENT SEED MIXTURE(S), PREPARE SOILS (FERTILIZERS AND LIME) AS FOR PERMANENT SEEDING, THEN SEED WITH TEMPORARY SEED MIXTURE AND MULCH, THEN OVERSOW THE PERENNIAL SEED MIXTURE INTO THE STUBBLE OF TEMPORARY VEGETATION AT THE NEXT APPROPRIATE SEEDING SEASON.

IF PERENNIAL SEED IS BEING SOWN INTO THE STUBBLE OF ACTIVELY GROWING TEMPORARY VEGETATION, MOW THE TEMPORARY VEGETATION TO REDUCE COMPETITION EITHER BEFORE OR IMMEDIATELY AFTER SOWING THE PERMANENT SEED.

MAINTENANCE: WATER AS NECESSARY TO ESTABLISH AND MAINTAIN VEGETATION. IN MOWED AREAS, MOW TO MAINTAIN GRASS HEIGHT BETWEEN 4 AND 6 INCHES TALL FOR FIRST TWO MONTHS OF GROWTH DURING THE ESTABLISHMENT YEAR, AND TO THE DESIRED HEIGHT THEREAFTER. IF STRING TRIMMERS ARE USED, TAKE MEASURES TO AVOID DAMAGE TO BARK OF TREES AND SHRUBS.

TABLE 4.1 COMPOST FILTER SOCK FABRIC MINIMUM SPECIFICATION

MATERIAL TYPE	3 MIL HDPE	5 MIL HDPE	5 MIL HDPE	MULTI-FILAMENT POLYPROPYLENE (MFFP)	HEAVY DUTY MULTI-FILAMENT POLYPROPYLENE (HDMFFP)
MATERIAL CHARACTERISTICS	PHOTO-DEGRADABLE	PHOTO-DEGRADABLE	BIO-DEGRADABLE	PHOTO-DEGRADABLE	PHOTO-DEGRADABLE
SOCK DIAMETERS	12" 18"	12" 18" 24" 32"	12" 18" 24" 32"	12" 18" 24" 32"	12" 18" 24" 32"
MESH OPENING	3/8"	3/8"	3/8"	3/8"	1/8"
TENSILE STRENGTH		26 PSI	26 PSI	44 PSI	202 PSI
ULTRAVIOLET STABILITY % ORIGINAL STRENGTH (ASTM G-155)	23% AT 1000 HR.	23% AT 1000 HR.		100% AT 1000 HR.	100% AT 1000 HR.
MINIMUM FUNCTIONAL LONGEVITY	6 MONTHS	9 MONTHS	6 MONTHS	1 YEAR	2 YEARS

TWO-PLY SYSTEMS

INNER CONTAINMENT NETTING	HDPE BIAXIAL NET
	CONTINUOUSLY WOUND
	FUSION-WELDED JUNCTURES
OUTER FILTRATION MESH	3/4" X 3/4" MAX. APERTURE SIZE
	COMPOSITE POLYPROPYLENE FABRIC (WOVEN LAYER AND NON-WOVEN FLEECE MECHANICALLY FUSED VIA NEEDLE PUNCH)
	3/16" MAX. APERTURE SIZE

SOCK FABRICS COMPOSED OF BURLAP MAY BE USED ON PROJECTS LASTING 6 MONTHS OR LESS

MAINTENANCE PROGRAM

ALL E&S CONTROLS SHALL BE MAINTAINED IN GOOD WORKING ORDER (CLEANED, REPAIRED, ETC.) UNTIL ALL DISTURBED TRIBUTARY AREAS ARE STABILIZED. ALL TEMPORARY E&S CONTROLS WILL REMAIN IN PLACE UNTIL A UNIFORM 70% PERENNIAL VEGETATIVE COVER IS ESTABLISHED. ONCE CONSTRUCTION IS COMPLETE, THE OWNER SHALL BE RESPONSIBLE FOR MAINTENANCE OF ALL PERMANENT FACILITIES.

- ALL TEMPORARY RUNOFF E&S CONTROLS SHALL BE INSPECTED AT LEAST AT THE BEGINNING AND END OF EACH DAY AND AFTER EACH RUNOFF EVENT TO MAINTAIN THEIR EFFECTIVENESS. ANY DAMAGED CONTROLS SHALL BE REPAIRED OR REPLACED BY THE END OF THE WORKING DAY.
- ROCK CONSTRUCTION ENTRANCE: ADDITIONAL STONE SHALL BE ADDED TO THE ROCK CONSTRUCTION ENTRANCE AND/OR ACCESS ROADS AS NEEDED TO MAINTAIN THEIR THICKNESS.
- SILT SOCK: ACCUMULATED SEDIMENTS SHALL BE REMOVED, AS REQUIRED, IN ALL CASES WHERE ACCUMULATIONS HAVE REACHED HALF THE ABOVE-GROUND HEIGHT OF THE SOCK. IF THE SOCK HAS BEEN DAMAGED, IT SHALL BE REPAIRED, OR REPLACED IF BEYOND REPAIR. THE FILTER MEDIA WILL BE DISPERSED ON SITE ONCE THE DISTURBED AREA HAS BEEN PERMANENTLY STABILIZED. ADHERE TO ALL MANUFACTURERS' RECOMMENDATIONS.
- INLET PROTECTION FILTER BAGS: ALL INLET PROTECTION FILTER BAGS SHALL BE CLEANED AND/OR REPLACED WHEN THE BAG IS HALF FULL IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. ALL DAMAGED FILTER BAGS SHALL BE REPLACED. THE ACCUMULATED SEDIMENT SHALL BE DISTRIBUTED EVENLY ALONG THE SITE AND STABILIZED.
- SEDIMENT BASIN/TRAP: INSPECT THE SEDIMENT BASINS ON AT LEAST A WEEKLY BASIS AND AFTER EACH RUNOFF EVENT. REPAIR CLOGGED OR DAMAGED SPILLWAYS IMMEDIATELY. THE ACCUMULATED SEDIMENT MUST BE REMOVED WHEN THE SEDIMENT STORAGE (SD) ELEVATION WITHIN THE TRAP/BASIN IS ACHIEVED. DISTRIBUTE THE ACCUMULATED SEDIMENT EVENLY ACROSS THE SITE AND STABILIZE.
- ALL SLOPES SHALL BE CHECKED FOR SIGNS OF EROSION AND/OR SEDIMENTATION.
- ALL DISCHARGE LOCATIONS SHALL BE INSPECTED TO ASCERTAIN THE EFFECTIVENESS OF THE CONTROLS. ADDITIONAL CONTROL MEASURES SHALL BE IMPLEMENTED AS NEEDED.
- DURING CONSTRUCTION, SEDIMENT REMOVED FROM THE EROSION CONTROL DEVICES SHALL BE DISPOSED OF BY SPREADING IT ONSITE. ONCE A UNIFORM 70% PERENNIAL VEGETATIVE COVER IS ESTABLISHED AND THE TEMPORARY E&S CONTROLS ARE REMOVED, ALL ACCUMULATED SEDIMENT WILL BE DISPOSED OF AT A PADEP APPROVED FACILITY.
- ALL SITE ENTRANCE AND EXIT POINTS SHALL BE INSPECTED FOR EVIDENCE OF OFF-SITE TRACKING OF MUD. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CLEAN STREETS OF MUD AND KEEP THE STREETS IN A CLEAN AND DUST-FREE CONDITION.
- SEEDED AND VEGETATED AREAS SHALL BE CHECKED REGULARLY TO INSURE THAT A GOOD STAND IS MAINTAINED. AREAS SHALL BE FERTILIZED AND RESEEDED AS NECESSARY.
- THE CONTRACTOR IS RESPONSIBLE FOR ALL MAINTENANCE AND INSPECTIONS, AND SHALL MAINTAIN RECORDS OF ALL INSPECTIONS. INSPECTIONS SHOULD BE LOGGED ON PADEP FORM 3150-FM-BWEW0083, DATED 2/2012 OR AS UPDATED, AND KEPT ONSITE AT ALL TIMES.

SEQUENCE OF CONSTRUCTION

THE RENOVATION AND RE-CONSTRUCTION OF THE EXISTING PANTHER HOLLOW POND WILL CONSIST OF ONE GENERAL PHASE OF CONSTRUCTION. ALL E&S CONTROL FACILITIES SHALL BE INSTALLED IN ACCORDANCE WITH THE APPROVED E&S CONTROL PLAN AND THE PADEP EROSION AND SEDIMENT POLLUTION CONTROL PROGRAM MANUAL DATED MARCH 2012.

A GENERALIZED CONSTRUCTION SEQUENCE IS PROVIDED BELOW. EACH CONSTRUCTION SEQUENCE IS INTENDED TO PROVIDE A GENERAL COURSE OF ACTION IN ORDER TO CONFORM TO THE APPLICABLE REGULATORY AGENCY REQUIREMENTS FOR TEMPORARY AND PERMANENT SOIL EROSION AND SEDIMENT POLLUTION CONTROL. ALL NECESSARY PARTS FOR PROPER AND COMPLETE EXECUTION OF WORK PERTAINING TO THIS PLAN, WHETHER SPECIFICALLY MENTIONED OR NOT, ARE TO BE PERFORMED BY THE CONTRACTOR. IT IS NOT INTENDED THAT THE DRAWINGS AND THIS REPORT SHOW EVERY DETAILED PIECE OF MATERIAL OR EQUIPMENT. THE CONTRACTOR SHALL COMPLY WITH ALL REQUIREMENTS LISTED IN THIS SECTION. THE CONTRACTOR MAY BE REQUIRED TO ALTER CONTROLS BASED ON EFFECTIVENESS OF CONTROLS OR DIFFERING CONDITIONS ENCOUNTERED. THE CONTRACTOR SHALL MAKE EVERY ATTEMPT TO MINIMIZE THE EXTENT AND DURATION OF EARTH DISTURBANCE ACTIVITY.

- AT LEAST 7 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES (INCLUDING CLEARING AND GRUBBING), THE OWNER AND/OR OPERATOR SHALL INVITE ALL CONTRACTORS, THE LANDOWNER, APPROPRIATE MUNICIPAL OFFICIALS, THE E&S PLAN PREPARER, THE PCSM PLAN PREPARER, AND A REPRESENTATIVE FROM THE ALLEGHENY COUNTY CONSERVATION DISTRICT TO AN ON-SITE PRECONSTRUCTION MEETING.
- UPON INSTALLATION OR STABILIZATION OF ALL PERIMETER SEDIMENT BMPs AND AT LEAST 3 DAYS PRIOR TO PROCEEDING WITH THE BULK EARTH DISTURBANCE ACTIVITIES, THE PERMITTEE OR CO-PERMITTEE SHALL PROVIDE NOTIFICATION TO THE DEPARTMENT OR AUTHORIZED CONSERVATION DISTRICT.
- AT LEAST 3 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, OR EXPANDING INTO AN AREA PREVIOUSLY UNMARKED, THE PENNSYLVANIA ONE CALL SYSTEM IN. SHALL BE NOTIFIED 1-800-242-1776 FOR THE LOCATION OF EXISTING UNDERGROUND UTILITIES.
- ALL EARTH DISTURBANCE ACTIVITIES SHALL PRECEDE IN ACCORDANCE WITH THE SEQUENCE PROVIDED ON THE PLAN DRAWINGS, DEVIATION FROM THE SEQUENCE MUST BE APPROVED BY THE ALLEGHENY COUNTY CONSERVATION DISTRICT OR BY THE DEPARTMENT PRIOR TO IMPLEMENTATION. EACH STEP OF THE SEQUENCE SHALL BE COMPLETED BEFORE PROCEEDING TO THE NEXT STEP, EXCEPT WHERE NOTED.
- LAYOUT THE LIMITS OF THE CONSTRUCTION SITE AND ESTABLISH BENCHMARKS AND REFERENCE POINTS.
- STAKE OUT THE LIMITS OF DISTURBANCE (6.1 ACRES) AS INDICATED ON THE CONSTRUCTION PLANS.
- INSTALL THE ROCK CONSTRUCTION ENTRANCES (2) AS SHOWN ON THE PLAN AND IN ACCORDANCE WITH THE STANDARD DETAIL.
- INSTALL ORANGE CONSTRUCTION FENCE AROUND AREAS OF PANTHER HOLLOW WHICH ARE NOT TO BE DISTURBED DURING CONSTRUCTION, AS SHOWN ON THE PLANS. ALSO CONSTRUCT ORANGE CONSTRUCTION FENCE AS SHOWN ON THE PLANS AND IN ACCORDANCE WITH THE STANDARD DETAIL.
- INSTALL SILT SOCK, 1,2,3, IN THE LOCATIONS SHOWN ON THE PLANS AND IN ACCORDANCE WITH THE STANDARD DETAIL BEING CAREFUL NOT TO DISTURB THE EXISTING WOODLANDS THAT ARE OUTSIDE OF THE DELINEATED LIMITS OF DISTURBANCE. ALL COMPOST FILTER SOCK SHALL BE INSTALLED PARALLEL TO THE CONTOURS.
- CLEARING, GRUBBING, AND EARTH WORK OPERATIONS WITHIN THE DRAINAGE AREAS TO THE PERIMETER CONTROLS MAY COMMENCE WHEN ALL PERIMETER CONTROLS ARE INSTALLED AND OPERATIONAL.
- BEGIN CLEARING AND GRUBBING ACTIVITIES NEEDED TO RE-CONSTRUCT THE EXISTING PANTHER HOLLOW LAKE, TAKING CARE NOT TO WORK BEYOND THE PERMIT BOUNDARY SHOWN ON THE PLAN. PLACE STRIPPED TOPSOIL IN THE TOPSOIL STOCKPILE AREAS DESIGNATED ON THE PLAN AND/OR REMOVE FROM SITE. STOCKPILE LOCATIONS MAY VARY IN THE FIELD, AND ADDITIONAL STOCKPILE LOCATIONS MAY BE USED AS NECESSARY. ALL TOPSOIL STOCKPILE AREAS SHALL BE FULLY ENCLOSED WITH SILT SOCK AS PER THE STANDARD DETAIL. INSTALL THE CONCRETE WASHOUT FACILITY AS SHOWN ON THE PLANS AND IN ACCORDANCE WITH THE STANDARD DETAIL.
- PERFORM CUT AND FILL OPERATIONS TO BRING THE PANTHER HOLLOW POND SITE TO THE PROPOSED FINAL SUBGRADE ELEVATIONS. UTILIZE ROCK FILL UNDERDRAINS, AS NECESSARY, TO CARRY THE IMPACTED EXISTING LAKE AND ANY ENCLOSED GROUNDWATER THROUGH THE PROPOSED GRADING. STABILIZE STAGING AREA AS SOON AS FINAL SUBGRADE ELEVATIONS ARE REACHED. RE-GRADE TO DESIGN GRADES AND UTILIZE A PUMP AND FILTER BAG TO DEWATER THE LAKE DURING CONSTRUCTION.
- CONSTRUCT PERMANENT BERM ON THE WESTERN SIDE OF PANTHER HOLLOW LAKE WITH APPROPRIATE SPILLWAY AS SHOWN ON THE PLANS AND IN ACCORDANCE WITH THE STANDARD DETAIL.
- BEGIN ROUGH GRADING ON SITE AND ALL FILL AREAS SHALL BE PLACED AND COMPACTED ACCORDING TO THE PROJECT EARTHWORK SPECIFICATIONS. CONSTRUCT FILL KEYS AND SUBSURFACE DRAINS AS SHOWN ON THE CONSTRUCTION DRAWINGS AND AS NECESSARY DURING EARTHWORK. PLACE TOPSOIL AND INSTALL EROSION CONTROL BLANKETS ON ALL SLOPES 3H:1V OR GREATER IN ACCORDANCE WITH THE STANDARD DETAIL. AT THE END OF EACH WORKING DAY NO MORE THAN 10 FEET OF SOIL SHALL BE EXPOSED WITHOUT BLANKET ON ANY PERMANENT SLOPES STEEPER THAN OR EQUAL TO 3H:1V. IMMEDIATE STABILIZATION IS REQUIRED UPON TEMPORARY CESSATION OF WORK, 4 OR MORE DAYS, OR AS SOON AS GRADED AREA REACHES FINAL GRADE.
- AS FILL SLOPES GRADES ARE ACHIEVED BACK-CUT SLOPES TO DIVERT THE RUNOFF TO THE BMP'S SHOWN ON THE PLANS.
- AS DISTURBED AREAS WITHIN A PROJECT APPROACH FINAL GRADE, PREPARATIONS SHOULD BE MADE FOR SEEDING AND MULCHING TO BEGIN. IN NO CASE SHOULD AN AREA EXCEEDING 15,000 SQUARE FEET WHICH IS TO BE STABILIZED BY VEGETATION, REACH FINAL GRADE WITHOUT BEING SEEDDED OR MULCHED.
- FINE GRADE AND STABILIZE ALL AREAS OF THE SITE. ALL UNPAVED DISTURBED AREAS SHALL BE STABILIZED IMMEDIATELY WITH SEED AND MULCH ONCE GRADING IS COMPLETE OR WITHIN FOUR (4) DAYS ONCE THE CONSTRUCTION HAS BEEN COMPLETED. INSTALL THE APPROPRIATE EROSION CONTROL BLANKETS FOR ALL SLOPES STEEPER THAN 3:1.
- FILL SLOPES SHOULD BE SEEDDED AND MULCHED AT REGULAR VERTICAL INCREMENTS - 15 TO 25 FEET MAXIMUM - AS FILL IS BEING CONSTRUCTED. THIS WILL ALLOW THE BOTTOM OF THE FILL TO PROGRESS TOWARD STABILIZATION WHILE WORK CONTINUES ON THE UPPER PORTION, MAKING STABILIZATION EASIER TO ACHIEVE AND PROVIDING SOME VEGETATIVE BUFFERING AT THE BOTTOM OF THE SLOPE.
- NOTIFY THE LICENSED PROFESSIONAL OR THEIR DESIGNEE AT LEAST 2 DAYS PRIOR TO THE START OF THE OF THE STORMWATER MANAGEMENT SYSTEM CONSTRUCTION. THE LICENSED PROFESSIONAL OR THEIR DESIGNEE MUST BE PRESENT DURING THE LAKE RE-CONSTRUCTION.

TOPSOIL REPLACEMENT SPECIFICATIONS

- GRADED AREAS SHOULD BE SCARIFIED OR OTHERWISE LOOSENED TO A DEPTH OF 3 TO 5 INCHES TO PERMIT BONDING OF THE TOPSOIL TO THE SURFACE AREAS AND TO PROVIDE A ROUGHENED SURFACE TO PREVENT TOPSOIL FROM SLIDING DOWN THE SLOP.
- TOPSOIL SHOULD BE UNIFORMLY DISTRIBUTED ACROSS THE DISTURBED AREA TO A DEPTH OF 4 TO 8 INCHES MINIMUM, 2 INCHES ON FILL OUTSLOPES.
- SPREADING SHOULD BE DONE THAT SODDING/SEEDING CAN PROCEED WITH A MINIMUM OF ADDITIONAL PREPARATION OR TILLAGE.
- IRREGULARITIES IN THE SURFACE RESULTING FROM TOPSOIL PLACEMENT SHOULD BE CORRECTED IN ORDER TO PREVENT FORMATION OF DEPRESSIONS UNLESS SUCH DEPRESSIONS ARE PART OF THE PCSM PLAN.
- TOPSOIL SHALL NOT BE PLACED IF TOPSOIL OR SUBSOIL IS FROZEN OR MUDDY, EXCESSIVELY WET, OR IN A CONDITION THAT MAY OTHERWISE BE DETRIMENTAL TO PROPER GRADING AND SEEDBED PREPARATION.
- COMPACTED SOILS SHOULD BE SCARIFIED 6 TO 12 INCHES ALONG CONTOUR WHEREVER POSSIBLE PRIOR TO SEEDING.

TABLE 11.1 TOPSOIL REPLACEMENT SPECIFICATIONS

DEPTH (in)	PER 1,000 SQUARE FEET	PER ACRE
1	3.1	134
2	6.2	268
3	9.3	403
4	12.4	537
5	15.5	672
6	18.6	806
7	21.7	940
8	24.8	1,074

TABLE 4.2 COMPOST FILTER SOCK STANDARDS


ORGANIC MATTER CONTENT	25%-100% (DRY WEIGHT BASIS)
ORGANIC PORTION	FIBROUS AND ELONGATED
pH	5.5-8.5
MOISTURE CONTENT	30%-60%
PARTICLE SIZE	30%-50% PASS THROUGH 3/8" SIEVE
SOLUBLE SALT CONCENTRATION	5.0 dS/M (MMHOS/CM) MAXIMUM

DRAFT

PRELIMINARY NOT FOR CONSTRUCTION

REVISION RECORD

NO	DATE	DESCRIPTION



CITY OF PITTSBURGH
DEPARTMENT OF PUBLIC WORKS
PITTSBURGH WATER & SEWER AUTHORITY
PITTSBURGH, ALLEGHENY COUNTY, PA

DRAWN BY: LJK/KPK	CHECKED BY: KPK	APPROVED BY: KPK
DATE: OCTOBER 2019	DWG SCALE:	PROJECT NO: 18-840
EROSION AND SEDIMENT CONTROL PLAN		DRAWING NO.: C903

S:\customers\2019\18-840_CEC_MWP\6_Engineering-Permitting\From CEC\CAD Design\Title (Revised) stormwater networks grading as limits\E&S Design Drawing\178889R-C901-CE_MWP\DWG\178889R-C901-CE_MWP.dwg